

# Agenda for 141<sup>st</sup> OCC Meeting

Date: 18.01.2018

Eastern Regional Power Committee
14, Golf Club Road, Tollygunge
Kolkata: 700 033

### **Eastern Regional Power Committee**

Agenda for 141st OCC Meeting to be held on 18th January, 2018 at ERPC, Kolkata

### Item no. 1: Confirmation of minutes of 140<sup>th</sup> OCC meeting of ERPC held on 19.12.2017

The minutes of 140<sup>th</sup> OCC meeting were uploaded in ERPC website and circulated vide letter dated 27.12.2017 to all the constituents.

Members may confirm the minutes.

### **PART A: ER GRID PERFORMANCE**

### Item no. A1: ER Grid performance during December, 2017

The average consumption of Eastern Region for December - 2017 was 319. Eastern Region has achieved maximum energy consumption of 331 Mu on 07<sup>th</sup> December-17. Total Export schedule of Eastern region for December - 2017 was 2378.5 Mu, whereas actual export was 2105.7 Mu.

### **ERLDC** may present the performance of Eastern Regional Grid covering the following:

- 1. Over drawal/under injection by ER Entities
- 2. Performance of Hydro Power Stations during peak hours
- 3. Performance of ISGS during RRAS

### Item no. A2: Commissioning of new transmission elements in Eastern Region

The details of new units/transmission elements commissioned in the month of December - 2017 based on information furnished by the constituents are depicted below:

- 1. 125 MVAr B/R III at Jamshedpur charged for the first time in parallel with 50 MVAr BR I at 18:12 Hrs. of 02/12/17.
- 2. 400/220 kV, 315 MVA ICT # 3 at Jamshedpur charged for first time (loading) at 17:43 hrs. of 11/12/17.
- 3. 400 kV Jharsuguda IB\_OPGC # I charged for first time at 19:05 hrs. of 19/12/17.
- 4. 400 kV Bus # 2B at IB\_OPGC charged for the first time at 19:05 hrs. of 19/12/17.
- 5. 400 kV Jharsuguda IB\_OPGC # II charged for the first time at 19:22 hrs. of 19/12/17.
- 6. 400 kV Bus # 1B at IB OPGC charged for the first time at 19:22 hrs. of 19/12/17.
- 7. 220 kV Atri Pandiabili # II charged and loaded for the first time at 18:53 hrs. of 19/12/17.
- 8. 220 kV Samagara Pandiabili # II charged and loaded for the first time at 19:33 hrs. of 19/12/17.
- 9. 400/220 kV, 315 MVA ICT # 3 at New Chanditala charged for first time (loading) at 16:09 hrs. of 20/12/17.
- 10. 400kV Raigarh Jhasuguda 4 (LILO of 400kV Rourkela- Raigarh 4 at Jhasuguda) charged for first time at 00:18 hrs. of 31/12/17.

### Constituents may update.

### Item no. A3: Persistent over drawl by West Bengal and Odisha

Over drawl figure of West Bengal and Odisha from 01-01-2018 to 07-01-2018 are shown below:

State	West Beng	ıal	Odisha		
Date	Over Drawl (MU)	Max. Over Drawl (MW)	Over Drawl (MU)	Max. Over Drawl (MW)	
01-01-18	0.517	328	1.718	479	
02-01-18	-0.017	301	1.977	571	
03-01-18	1.36	400	1.97	450	
04-01-18	1.385	561	0.900	411	
05-01-18	0.068	354	1.655	435	
06-01-18	0.609	286	1.995	461	
07-01-18	0.746	467	2.643	516	

In 140<sup>th</sup> OCC, over drawl pattern of West Bengal and Odisha was deliberated in detail. Some improvement in West Bengal and Odisha Drawl pattern has been observed during December and up to 7<sup>th</sup> January-2018. West Bengal average over drawl quantum was reduced to 1 mu during above mentioned period where as for Odisha over drawl quantum is around 2 mu per day. In view of above, still there is some scope to maintain drawl as per schedule during morning and evening peak hour to avoid such quantum over drawl.

### ERLDC may present. WBSETCL and Odisha may explain.

### Item no. A4: Reactive Power performance of Generators

Generating stations have been monitored for certain sample dates in the month of December, 17.

<b>Power Plant</b>	Max and Min Voltage	Date for monitoring (Dec 17)
	observed for Dec 17 (KV)	
Farakka STPS	425, 412	4,12
Khalgaon STPS	422, 417	14,15
Talcher STPS	414, 395	2,7
Teesta-v	420,396	15,26
Bakreshwar TPS	411, 401	10, 29
Kolaghat TPS	428, 405	4,6
Sagardighi TPS	426, 411	4,6
MPL	421, 410	4,6
Mejia-B	424, 412	4,10
DSTPS	423, 413	15,28
Adhunik TPS	425, 410	1,18
Barh	427, 409	2,4
JITPL	417, 409	4,18
GMR	414, 408	1,17

HEL	430,402	2,11
Kodarma	422, 409	7,28

### ERLDC may present the reactive performance.

### Item no. A5: Restricted Governor /Free Governor Mode Operation of generators in ER

(1) On 09-12-17, 12:58 Hrs, TBC breaker blasted at 400 kV Padghe S/S. As a result all emanating feeders from Padghe tripped and about 1400MW load was thrown off. Response observed in respect of various ISGS / IPPs would be presented by ERLDC.

In Petition No. 84/MP/2015, Date of order: July 31, 2017 section 23 (a), CERC noted

- ... the Commission, starting from the month of September, 2017 shall be closely watching the primary response of ISGSs as reported by POSOCO/NLDCs.
- At the State level, SLDCs shall report the frequency response of intra-State generators to the concerned SERCs."

To comply with this order, ERLDC is sending the primary response of all ISGS/IPP in the region to NLDC. Reports from all RLDCs are in turn compiled by NLDC and submitted to the Hon'ble Commission.

SLDCs may please confirm whether similar reports are being submitted by them to their respective SERCs.

### **ERLDC** may present. **SLDCs** may update.

### Item no. A6: Bus Splitting operation of 400kV Maithon Sub-station

ERLDC vide mail dated 8<sup>th</sup> January 2018 informed that split-bus mode operation of Maithon 400kV S/stn was implemented w.e.f. 12:23 Hrs of 05-01-18, by opening the sectionalizing CBs between bus sections A and B. Disposition of line/ICTs are as follows:

SI No	Maithon – B (Bus 2 & 4)	Maithon-A (Bus 1 & 3)
1	400 kV Maithon- MPL D/C	2 x 500 MVA 400/220kV ICT
2	400 kV Maithon Ranchi	400 kV Maithon-Mejia I & II
3	400 kV Maithon-Raghunathpur	400 kV Maithon-Gaya D/C
4	125 MVAR B/Reactor-2	400 kV Maithon-Kahalgaon-II
5	400 kV Maithon-Parulia (Durgapur) D/C	400 kV Maithon-Jamshedpur
6	400 kV Maithon-Kahalgaon -I	125 MVAR B/Reactor-1
7	400kV Maithon – Mejia-III	

Power flow before and after the bus spilitting are enclosed at **Annexure-A6**.

### Members may note.

### Item no. A7: UFR operation during the month of December'17

System frequency touched a maximum of 50.25 Hz at 22:00 Hrs of 03/12/17 and a minimum of 49.7 Hz at 09:19 Hrs of 15/12/17. Hence, no report of operation of UFR has been received from any of the constituents.

### Members may note.

### Item no. A8: Non-compliance of directions issued by SLDC

Vide clause no 5.5.1.(c)(h) of IEGC, non-compliance of SLDC directions by SEB/Distribution licenses/bulk consumers to curtail overdrawal are to be reported to ERLDC for incorporating the same in weekly report to be prepared and published by ERLDC.

All SLDCs are to inform ERLDC the instances of non-compliance of SLDC directions by SEB/Distribution licenses/bulk consumers to curtail overdrawal, within two days after the day of operation.

No report from any constituent has yet received. Hence, ERLDC would be considering 'Nil' report for all constituents for December'17.

### Members may note.

Item no. A9: Grid incidences during the month of December, 2017

Sr No	GD/ GI	Date	Time	Summary	Load loss (MW)	Gen loss (MW)
1	GI-II	06/12/2017	09:09	At 09:09 hrs due to operation of bus bar differential protection of both bus I & II at New Chanditala, All elements connected to New Chanditala i.e. 400 kV Jeerat-New Chanditala S/C, 400 kV KTPP - New Chanditala S/C 400 kV New Chanditala - Kharagpur D/C along with both bus I& II and 400/220 kV ICTs at New Chanditala tripped.		0
2	GD-I	06/12/2017		At 18:22 hrs, total power failure occurred at 220/132 kV Madhepura S/S due to tripping of 220 kV Madhepura - Purnea D/C resulting interruption of supply at Supaul Sonebarsa, Madhepura, Saharsa, Kushaha(Nepal) & Udaikashigunj.		0
3	GD-I			At 10:57 hrs, all lines connected to 400/132 kV Motihar S/S tipped due to operation of bus bar protection of both bus I & II. It was reported that motorized earth switch connected to main bay of 125 MVAr B/R I (connected to bus II) became grounded resulting operation of bus bar operation at both buses.	174	0
4	GD-I	13/12/2017	16:43	At 16:43 hrs 220 kV Patna - Sipara D/C and 220 kV Khagul Sipara S/C tripped due to spurious bus bar protection operation at Sipara S/S resulting total power failure at Sipara S/S.	226	0
5	GD-I	13/12/2017	17:19	After the initial disturbance at Sipara at 16:43 hrs, during restoration 220 kV Patna Sipara D/C tipped again at 17:19 hrs while extending power to Khagul and supply to Sipara S/S got interrupted again.	100	0
6	GD-I	15/12/2017	06:01	At 06:01 hrs 132 kV Malda - Malda - II tripped from both ends ( PG end: R-N, F/C 9 kA; WB end: R-B-N, 11.38 km). At same time 132 kV Malda - Malda - I (R-B-N, 3.69 km from WB end) also tripped from WB end. This circuit was later manually opened from PG end. 220/132 kV ATR I & II at Malda (PG) also tripped on operation of back up directional O/C relay.	55	0
7	GD-I	20/12/2017	13:52	220 kV Muzaffarpur - Hazipur - I was under shut down. At 13:52 hrs 220 kV Muzaffarpur - Hazipur - II tripped in Y-B-N fault resulting total power loss at Hazipur, Siwan Chapra & Amnour.	130	0
8	GD-I	22/12/2017	10:49	220/132 kV ICT - II at Purnea (PG), 132 kV Purnea - Purnea - II and 132 kV Purnea - Kishangunj were under shutdown. At 10:49 hrs, 220/132 kV Purnea S/S became dead due to tripping of 132 kV Purnea - Purnea - I & II	90	0

9	GD-I	22/12/2017	17:10	220 kV Gaya - Bodhgaya D/C were under shutdown. 220	135	0
				kV Biharshariff - Khijasarai - II tripped from both ends		
				(BSF end: Y-N, Z-I, 1.6 km, 18 kA; Khijasarai end: Y-N		
				36.4 km) due to Y phase jumper snapping at location no		
				237. At the same time, 220 kV Biharshariff - Khijasarai - I		
				tripped from the both ends (BSF end: Y-N, O/C, faul		
				duration: 18.39 ms; Khijasarai end: E/F) and 220/132 kV		
				ATR - II at Biharshariff tripped due to operation of		
				differential relay (Fault duration 73 ms).		

Members may note.

### Item no. A10: Reporting of voltage deviation indices (VDI) for select S/Stns in ER

ERLDC submitted the Voltage Deviation Index (VDI) of selected 400 kV Sub-stations for December, 2017 of Eastern Region which is enclosed at **Annexure- A10**.

Members may note.

### PART B: ITEMS FOR DISCUSSION

### Item No. B.1: Methodology for Submitting the Status of New Transmission Elements/ Generating Units to be Commissioned within the State

For clear visibility of the Eastern Region networks and better system operation, all the new transmission elements (ISTS & STU links) need to be updated regularly. The commissioning of new transmission elements of ISTS lines has been processed and updated by RLDC whereas commissioning of STU lines has been processed by SLDCs. However, commissioning status of new STU lines of states has not been updated to ERLDC and ERPC regularly. Sometime SLDCs used to submit the status of their new commissioning of elements during OCC meeting. To regularize the process following methodology need to be adopted:

- 1. Transmission elements/ Generating units expected to be commissioned during next month need to be submitted to ERLDC/ERPC in every OCC.
- 2. Detail parameters of new transmission element before commissioning need to be shared with RLDC.
- 3. Detail date and time of synchronization need to be updated on real time to ERLDC after commissioning of any new Transmission element/Generating unit.
- 4. SLDC SCADA team needs to configure the new element in their SCADA and share the same to ERLDC SCADA for network update.
- 5. List of the new transmission elements/ generating units commissioned during last month need to inform RLDC/RPC within 7<sup>th</sup> day of the current month, so that same to be updated in OCC.

### Members may discuss.

# Item No. B.2: Training on "Optimum calculation of transfer capability (ATC, TTC and TRM)" by International Consultant

CEA vide mail dated 21st December 2017 informed that M/S Powertech Labs Inc. (PLI) Canada is providing consultancy services in India. As per the contract 3 days training is arranged at ERPC, Kolkata from 19th to 21st February 2018. The training will be held at the ERPC Conference Hall, Kolkata. The training programme covers the following topics:

 Examination and recommendation of methodology for optimum calculation of transfer capability (TTC/ATC/TRM) in the planning and the operational horizons • Calculation of transfer capability (TTC/ATC/TRM) for entire country

# Constituents may nominate members preferably dealing with Transmission Planning and Grid Operation.

### Item No. B.3: Status of projects funded under PSDF schemes

In the PSDF review meeting, it was advised to RPCs to monitor the status of all the projects funded by PSDF. Therefore, constituents are requested to update the status of projects which are being funded by PSDF in the desired format.

SN	Name of Constituent	Name of Project	Date of approval from PSDF	Target Date of Completion	PSDF grant approved (in Rs.)	Amount drawn till date (in Rs.)	Latest status
1	WBSETCL	Renovation & up-gradation of protection system of 220 kV & 400 kV Substations in W. Bengal	31-12-14	January 2018	108.6 Cr	18.26 Cr.	100 % Supply is Completed 92% Erection is completed
2		Renovation & modernisation of transmission system for relieving congestion in Intra-State Transmission System.	22-05-17	19 months from date of release of 1 <sup>st</sup> instalment	43.37	Nil	Agreement signed. Bank A/c opened & PFMS mapping is in process.
3		Installation of switchable reactor at 400kV & shunt capacitors at 33kV	22-05-17	25 months from date of release of 1 <sup>st</sup> instalment	70.13	Nil	Agreement signed. Bank A/c opened & PFMS mapping is in process.
4	OPTCL	Renovation & Up-gradation of protection and control systems of Sub-stations in the State of Odisha in order to rectify protection related deficiencies.	10.05.15	10.05.17	162.5 Cr.	16.25 Cr + 8.91 Cr	Total contract awarded for Rs. 51.35 Cr
5	ERPC	Creation & Maintenance of web based protection database and desktop based protection calculation tool for Eastern Regional Grid	17.03.16	Project is alive from 30 <sup>th</sup> October 2017	20 Cr.	4.94 Cr. + 9.88 Cr.	1) Hardware supplied and installed. 2) SAT completed for pilot state 3) Protection database management software (PDMS) put in live w.e.f. 30.03.17. 4) Training on PDMS organised at ERPC, Odisha, Bihar, WBSETCL, Jharkhand and DVC.
6		Renovation and up-gradation of 220/132/33 KV GSS Biharsharif, Bodhgaya, Fatuha, Khagaul, Dehri -on-sone & 132/33 kV GSS Kataiya	11/5/201 5	Feb'2017	64.22 crore	23.68 crore	Project is on going. Contract awarded for Rs.71.37 Cr till date.
7	BSPTCL	Installation of capacitor bank at different 35 nos. of GSS under BSPTCL	5/9/2016	12 <sup>th</sup> March 2019	18.88 crore		Approved (triparty agreement among NLDC, Govt. of Bihar & BSPTCL is in under process)
8		Renovation & up-gradation of protection and control system of 12 nos. 132/33 KV GSS under BSPTCL.		31 <sup>st</sup> March 2018			Recommendation of appraisal committee is awaited. Estimated cost 54.69 crore.
9	DVC	Renovation and upgradation of control & protection system and replacement of Substation Equipment of 220/132/33 kV Ramgarh Substation	02.01.201	01.06.2019	25.96 Cr	2.596 Crore on 01.06.201 7	Work awarded for 28.07 crore.

10		Renovation and upgradation of control & protection system including replacement of substation equipment at Parulia, Durgapur, Kalyaneshwari, Jamshedpur, Giridih, Barjora, Burnpur, Dhanbad and Burdwan Substation of DVC		24 Months from the date of release of fund.	140.5 Cr.	installmen t of 14.05 Cr. received on 21.12.201	Work awarded for 6.45 crores
11	WBPDCL	Implementation of Islanding scheme at Bandel Thermal Power Station	10.04.201 7		1.39 Cr		Award placed to ABB. Material delivery by Dec, 17. Most of the materials have reached the site and the installation would commence soon.
12		Upgradation of Protection and SAS			26.09		Approved by Ministry of Power
13	OHPC	Renovation and up-gradation of protection and control system of 4 nos OHPC substations.			22.35 Cr		Tendering under progress.
14	Powergrid	Installation of STATCOM in ER		June 2018	160.28 Cr	63.028 Cr	work is in progress, eexpected to complete by June 2018
15	JUSNL	Renovation and up-gradation of protection system		138.13 crores			Approved by Appraisal Committee.
16a	ERPC	Training for Power System Engineers					The proposal was approved by Appraisal Committee. The
16b		Training on Power market trading at NORD POOL Academy for Power System Engineers of Eastern Regional Constituents					proposal was sent to CERC. CERC has sought some queries from the Appraisal Committee.

In the 5<sup>th</sup> Meeting of Monitoring Group of PSDF held on 21.10.2017, it was decided to hold the Monitoring Group meetings at regional level with participation of all the concerned entities of the region to review the progress of the projects/scheme being funded from PSDF.

The PSDF Monitoring Group meeting would be held at ERPC Conference Hall, Kolkata in 2<sup>nd</sup> week of February 2018.

### Respective constituents may update the status.

# Item No. B.4: Rectification of the SPS associated with tripping of any pole of HVDC Talcher-Kolar.

During synchronisation of NEW grid with SR grid, to limit the surplus power likely to be wheeled to SR through ER and WR, in the event of single or bi-pole outage of 500 kV Talcher-Kolar HVDC, arrangement for 600 MW generation reduction in ER (200 MW each at SEL, GMR and JITPL) by sending digital signals from Talcher STPS was made, apart from the pre-existing reduction/tripping of TSTPS-II generation.

To implement this SPS, signal is transmitted from Talcher to the concedrned generating stations. In case of Sterlite/VAL signal was transferred through PLCC link from 400 kV Rourkela substation of POWERGRID. However after removing LILO of Rourkela-Jharsuguda at SEL, this link is no more available. In view of revised connection it is proposed that link for sending SPS signal to SEL / VAL may be re-established either via Jharsuguda or via Meramandali.

### Members may discuss.

### Item No. B.5: Failure of Real time telemetry

On 06<sup>th</sup> December 2017 at 17:26 hours, there was failure of real time SCADA data of 17 nos Central Sector station to ERLDC due to communication failure between Malda – Farakka OPGW link. The real time data restored at 09:37 Hours of 07th December 2017. Reports of the above mentioned event is attached in **Annexure –B5.1**.

The real time SCADA data of North Bengal & Sikkim is totally dependent on availability of Malda – Farakka communication link. The path redundancy of Malda – Farakka communication link must be planned and implemented by POWERGRID so that such failure could be avoided

On 14<sup>th</sup> December 2017 at 12:52 hrs, there was complete outage of real time SCADA telemetry due to fibre issue between Jeerat-Kasba Section. Report is enclosed at **Annexure- B5.2**.

### Members may discuss.

# Item No. B.6: Recovery of loss due to schedule revision during flodding of Kishanganj S/S of PGCIL-Teesta Urja Ltd.

Due to flooding at Kishanganj S/S of PGCIL, the IEX schedule of Teesta-III HEP and other Projects was directed to be revised from 10:00 hours to 24:00, hours on 13.08.2017. However, vide subsequent communications, the curtailment of schedule was initially directed to start from 10.00 hrs, which got changed to 10.30 hrs and again to 10.00 a.m. However, the IEX schedule which had got curtailed from 10.30 hrs could not get revised to 10.00 hrs leading to the Teesta-III (and other Projects) being penalized under DSM for two time blocks from 10.00 hrs to 10.30 hrs.

### Members may discuss.

# Item No. B.7: Revision of final schedule of Dikchu HEP and revocation of UI penalty inflicted on 13.08.2017- Dikchu

On 13.08.2017, Dikchu was advised by ERLDC through mail and phone to back down the generation to Zero w.e.f 10:00 hrs, 13.08.2017, as all STOA & collective transactions were cancelled due to flooded condition at Kishanganj S/s. Dikchu plant was shut down promptly within 10:01 hrs.

The final schedule of Dikchu HEP was revised to Zero w.e.f 10:30 hrs by NLDC. The consequence was that as per final generation schedule data, although Dikchu was able to generate 96 MW in between 10:00 hrs to 10:30 hrs, Dikchu generation was Zero in real time incurring heavy UI penalization.

It is requested to consider the merit of the incidence and accord consent in revision of the final schedule of 13.08.2017 from 10:00hrs to 10:30 hrs to Zero in respect of Dikchu HEP.

### Members may discuss.

### Item No. B.8: PPA details for the years 2017-18 to 2019-20

CEA vide mail dated 21<sup>st</sup> November 2017 informed that it has been decided to estimate the demand and availability of power (energy and peak), initially for the year 2017-18 and subsequently for the years 2018-19 and 2019-20. In this regard, PPA details for the years 2017-18 to 2019-20 are required as per the format enclosed at **Annexure-B8**.

All the constituents furnish the data as per the format to CEA by email: rk.jena@gov.in.

In 140<sup>th</sup> OCC, Member Secretary, ERPC informed that PPA details of the utility constituents and generators are required by CEA to identify the capacities of the IPPs which are available for fresh PPAs as well as the utility constituents who may utilize these.

OCC advised all the constituents to send the PPA details for the years 2017-18 to 2019-20 as per the format to CEA vide email: rk.jena@gov.in with a copy to mserpc-power@nic.in.

### Constituents may update.

# Item No. B.9: Option for handling intra-day load/generation variation due to RE or otherwise.

Sub-Group under FOR Technical Committee on Grid Integration of Renewable Energy (RE), with reference to regional cooperation had a meeting on 18.8.2017 in CERC office, New Delhi. Record of proceedings is placed in **Annexure-B9**.

As decided in the meeting various options for handling intra-day load / generation variation due to RE or otherwise, as discussed in the meeting be circulated and discussed with Members of Regional Power Committees and feedback on the same may be provided to us to facilitate further deliberations and suitable recommendations by the FOR Technical Committee on Grid Integration of RE.

In 140<sup>th</sup> OCC, all the members were advised to submit their comments to ERPC vide mail (mserpc-power@nic.in) within ten working days.

Members may update.

### **PART C: ITEMS FOR UPDATE**

### Item no. C.1: Status of UFRs healthiness installed in Eastern Region

UFR Healthiness Certification for the month of December, 2017 has been received from CESC, WBSETCL, DVC, and BSPTCL.

JUSNL and OPTCL may submit.

### Item no. C.2: Status of Islanding Schemes healthiness installed in Eastern Region

At present, the following islanding schemes are in service:

- CESC as a whole Islanding Scheme, CESC
- 2. BkTPS Islanding Scheme, WBPDCL
- 3. Tata Power Islanding Scheme, Haldia
- 4. Chandrapura TPS Islanding Scheme, DVC
- 5. Farakka Islanding Scheme, NTPC

In 108<sup>th</sup> OCC meeting, respective constituents agreed to certify that the islanding schemes under their control area are in service on monthly basis.

In 134<sup>th</sup> OCC, JUSNL was advised to submit the healthiness certificate of the UFR and PLCC system related to Farakka islanding scheme at their end.

The healthiness certificate for Islanding Scheme for December, 2017 has been received from CTPS, DVC, BkTPS, Tata Power and CESC.

### NTPC and JUSNL may submit.

### Item no. C.3: Healthiness of SPS existing in Eastern Region

GMR, JITPL, Chuzachen, CESC, & NTPC (TSTPS) have submitted the healthiness certificate for the month of December, 2017.

In 136<sup>th</sup> OCC, members felt that healthiness certificate for SPS of 132 kV Muzaffarpur-Dhalkebar D/C line may also be submitted on monthly basis and advised Powergrid to submit the healthiness certificate in every OCC meeting.

In 138<sup>th</sup> OCC, ERLDC informed that Tashiding HEP is also included under Rangpo SPS, two units of Tashiding HEP will trip on actuation of SPS. However, it will be reviewed in coordination with other generators covered in the SPS.

Powergrid vide mail dated 11-01-2018 informed that the SPS system at HVDC, Talcher and Angul are healthy but SPS system of Rourkela S/S is not in service after the isolation of LILO connectivity with Sterlite.

Vedanta, and Powergrid may submit the healthiness certificate for December 2017.

Teesta-III, Jorethang & Dikchu may submit the healthiness certificate for Rangpo SPS as decided in special meeting of 21.06.2017.

# Item no. C.4: Continuous receipt of generation back down signal on shutdown of HVDC Talcher-Kolar single pole.

On 08/01/18 HVDC Talcher-Kolar Pole-I was taken under shut down for maintenance activities. To prevent any unwarranted backing down/tripping at JITPL/GMR, SPS was by-passed on a temporary basis at the respective generator ends, just prior to availing of the shutdown. However, after the shutdown was availed, the SPS could not be taken back into service as there was continuous receipt of backing down signal at the respective generator ends. Hence, the SPS had to be kept by-passed throughout the shutdown period even though Pole-II was in service. It was reported that the continuous backing down signal could not be disabled at HVDC, Talcher end.

Similar continuous transmission of SPS signal from TSTPS was observed and reported earlier also. In 110<sup>th</sup> OCC, Powergrid informed that they are planning to place a timer circuit to rectify the problem.

However, necessary rectification of the SPS is still pending.

Powergrid may update.

### Item no. C.5: Controlling overdrawal of states by disconnection of radial feeders -ERLDC

In accordance with IEGC sections 5.4.2 (c) and 5.4.2 (f), feeders for disconnecting demand of every state in the order of their priority for switching off, were identified in the past. However, with growth of network interconnection and load as well as change of load distribution (if any) during the intervening period, it is felt that the list needs reviewing.

All constituents are requested to furnish views regarding their respective identified feeders and indicate the expected load (average and peak) that would be disconnected by switching off the feeders, so that the list can be finalized at the earliest.

Updated list of feeders is yet to be received from OPTCL and DVC.

**OPTCL** and **DVC** may update.

### Item no. C.6: Implementation of Automatic Demand Management Scheme (ADMS)-ERLDC

The latest status along with proposed logic as follows:

SI No	State/Utility	Logic for ADMS operation	Implementation status/target	Proposed logic (if different from under implementation logic)
1	Bihar	F <49.7 AND deviation > 12 % or 150 MW	Not Known	F <49.9 AND deviation > 12 % or 150 MW
2	Jharkhand	Yet to provied	9 Months	
3	DVC	F <49.7 AND deviation > 12 % or 150 MW	17.06.2016	F <49.9 AND deviation > 12 % or 150 MW
4	Odisha	1. System Frequency < 49.9 Hz 2. Odisha over-drawl > 150 MW 3. DISCOM over-drawl > (40 MW)	10 Months	Logic 2 and 3 is AND or OR, in case it is AND then ADMS may not operated when discom are in schedule but GRIDCO is overdrawing due to less generation at state embedded generators
5	West Bengal	F <49.7 AND deviation > 12 % or 150 MW	25.11.16	F <49.9 AND deviation > 12 % or 150 MW

### Members may update.

### Item no. C.7: Commissioning of 220 kV Patna-Sipara third ckt.

Major load of Capital city Patna is fed from 220 kV Sipara Substation, Further Sipara is conneted with Khagaul as well as Fatuah at 220 kV level. These are also major load centers normally fed in radial mode from Patna (except Fatuah, which is usually supplied radially from Biharshariff). This causes very high loading of 220 kV Patna-Sipara D/C and it did not satisfy N-1 Contingeny criteria for most of the time in last quarter.

The third circuit of 220kV Patna-Sipara line is expected to be commissioned soon, which will help in relieving the loading on other two lines. Further with commissioning of 220 kV Patna-Sipara T/C 220 kV Khagul-Arrah-Pusauli loop may be kept close, which will help in improving system reliability and maintaining better voltage regulation in and around that area.

In view of above BSPTCL may expedite commissioning of 220 kV Patna-Sipara third ckt.

In 140<sup>th</sup> OCC, BSPTCL informed that the line was tripped on busbar protection. Testing is in progress and the line would be commissioned by 31<sup>st</sup> December 2017.

### **BSPTCL** may update the latest status.

### Item no. C.8: Reactor at 400kV Behrampur

In 140<sup>th</sup> OCC, Powergrid informed that in view of high voltage at Behrampur they have diverted one 125MVAR reactor to Behrampur and the reactor will be installed by end of December 2017.

### Powergrid may update.

### Item no. C.9: Long outage of 400 kV Barh - Motihari D/C

400 kV Barh – Motihari – D/C were out since 14th Aug, 2017 as 24 numbers of towers were submerged in Gandak River due to flood like situation. Right Now Motihari is drawing radial power from Gorakhpur S/S of Northern region through 400 kV Gorakhpur – Motihari D/C. Due to outage of 400 kV Barh - Motihari D/C, one inter regional link between Eastern and Northern region was out, which need to be restored with utmost priority to maintain all India reliable and safe power system operation.

DMTCL vide letter dated 11<sup>th</sup> December 2017 informed that the ERS Towers needs to be erected on the river bed for restoration of the line. However due to non-availability of proper anchorage, the erection of ERS towers is taking more than the anticipated time.

Also, there is no approach available for shifting of manpower & material at the locations and the same is being done with the help of boats.

In view of the above specified challenges being faced at site, this is to inform you that both the Ckts of above transmission line will be restored by 31<sup>st</sup> Dec 2017.

### **DMTCL** may update.

### Item no. C.10: Repeated tripping of 220kV Chuka-Birpara D/c line

In 60<sup>th</sup> PCC, meeting Powergrid explained that the line is in lightning prone area. The line is getting tripped due to Insulator failures. Powergrid added that line insulators of part of the line which is belongs to Powergrid have been replaced with polymer insulators. The insulator failures during lightning have been reduced. However, the line is getting tripped due to failure of porcelain insulators in 39.8 km stretch which is belongs to Bhutan.

In 138<sup>th</sup> OCC, DGPC informed that BPC is the owner of part of the line which is belongs to Bhutan. They have already replaced porcelain insulators of 7 to 8 towers with polymer insulators.

In 140<sup>th</sup> OCC, BPC representative informed that supply order has been placed for insulator replacement and the material will be delivered by January, 2018. The replacement of insulators would be completed by April, 2018.

### BPC/DGPC may update.

# Item no. C.11: Repair/Rectification of tower at location 79 of 132kV Rangpo-Melli D/c line and Chuzachen(Rangpo)-Gangtok transmission lines - Powergrid

Powergrid informed that their patrolling team has observed bent in part of tower no. 79 of 132kV Rangpo-Melli D/c line and Chuzachen(Rangpo)-Gangtok transmission lines which may further degrade the condition of tower.

In 137<sup>th</sup> OCC, Powergrid informed that tower no. 79 of 132kV Rangpo-Melli D/c line and Chuzachen(Rangpo)-Gangtok transmission lines falls under the jurisdiction of Energy & Power Department, Govt. of Sikkim.

Powergrid added that the issue has been informed to Sikkim vide letter dated 20<sup>th</sup> September 2017.

ERPC has communicated the issue to Sikkim vide letter dated 13<sup>th</sup> December 2017.

### Powergrid and Sikkim may update.

### Item no. C.12: Replacement of CT at both ends of 400kV Jeerat-Baharampur Line

In 135<sup>th</sup> OCC, Powergrid agreed to replace 1000/1A CT by 2000/1 A CT at both ends of 400kV Jeerat-Baharampur Line.

### WBSETCL and Powergrid may update.

### Item no. C.13: Status of Installation of STATCOM in Eastern Region

In the 15<sup>th</sup> meeting of SCM it was agreed to install STATCOM in combination with mechanically switched Reactors (MSR) and Capacitors (MSC) and co-ordinated control mechanism of MSCs and MSRs at Ranchi, Rourkela, Jeypore and Kishanganj substations in Eastern Region.

The matter was again discussed in the 28th ERPC/TCC meeting held on 12th -13th September, 2014 at Goa, wherein, it was decided that POWERGRID may go ahead with implementation of the STATCOM project in Eastern Region with debt – equity ratio of 70:30 funding. The debt part should be refunded through PSDF and Equity Component (30%) to be funded by POWERGRID to be recovered through regulated tariff mechanism. CTU should initiate the process of availing fund from PSDF.

Powergrid updated the latest status as follows:

SI No	Location /Sub- Station of POWERGRID	STATCOM - Dynamic Shunt Controller	Mechanically Switched Compensation SI. (MVAr)		Latest status
140	in ER	(MVAr)	Reactor (MSR)	Capacito r (MSC)	
1	Rourkela	±300	2x125		Expected to complete by Mar 2018
2	Kishanganj	±200	2x125		70% civil work completed. 30% switchyard equipment supplied. Expected to complete by June 2018
3	Ranchi(New)	±300	2x125		80% civil work completed. All switchyard equipment, reactors and 3 transformers supplied.  Expected to complete by April 2018
4	Jeypore	±200	2x125	2x125	Expected to complete by June 2018

### Powergrid may update.

# Item no. C.14: 220 kV inter-connecting lines of OPTCL with 400/220 kV Bolangir (PG), Keonjhar & Pandiabil S/s

PGCIL has already commissioned the 2x315MVA 400/220kV Bolangir S/s by LILOing of 400kV Meramandali-Jeypore S/C line and 400/220 kV Keonjhar S/s with an objective of supplying power from ER grid to its adjoining areas in Odisha.

In last OCC, OPTCL updated the completion schedule of inter-connecting system as follows:

SI. No.	Name of the transmission line	Completion schedule
1.	2x315MVA 400/220kV Bolangir S/s	
a.	LILO of one circuit of Sadeipalli-Kesinga220 kV D/C	Only 7 towers left (Severe ROW
	line at Bolangir S/S	problem). By June, 2018.
2.	400/220 kV Keonjhar S/S	
a.	Keonjhar (PG)-Keonjhar (OPTCL) 220 kV D/C line	By Mar, 2018.
b.	Keonjhar (PG)-Turumunga(OPTCL) 220kV D/C line	By 2019.
3.	400/220kV Pandiabil Grid S/s:	
a.	Pratapsasan(OPTCL)-Pandiabil(PG) 220 kV D/C line	By Mar, 2018.

### **OPTCL** may update.

# Item no. C.15: 220 kV inter-connecting lines of JUSNL with 2x315 MVA, 400/220 kV sub-stations at Chaibasa, Daltongani & Dhanbad

In last OCC, JUSNL updated the latest status as follows:

SI. No.	Name of the transmission line	Completion schedule
1.	Chaibasa 400/220kV S/s	
a.	Chaibasa (JUSNL) – Ramchandrapur (JUSNL) 220kV D/c	By Dec, 2017 Bays at Ramchandrapur switchyard are not yet ready and the line is idle- charged from Chaibasa(JUSNL).
2.	Daltonganj 400/220/132kV S/s:	
a.	Daltonganj (POWERGRID) – Latehar 220kV D/c	By Dec, 2017. Forest clearance is pending, it will take time.
b.	Daltonganj (POWERGRID) – Garhwa 220kV D/c	May, 2018. Forest clearance is pending, it will take time.
С	Daltonganj (POWERGRID) – Daltonganj (JUSNL) 132kV D/c	Dec, 2018. Forest clearance is pending, it will take time.
d	Daltonganj (POWERGRID) – Chatarpur/Lesliganj 132kV D/c	Matching with S/s, Forest clearance is pending, it will take time.
3.	Dhanbad 400/220 kV S/s: Awarded under TBCB	
a.	Dhanbad – Dhanbad (Govindpur) (JUSNL) 220kV D/c	Matching with S/s. Forest clearance is pending, it will take time.

JUSNL may update.

# Item no. C.16: 220 kV inter-connecting lines of WBSETCL with 400/220 kV, 2x315 MVA Alipurduar & 2x500 MVA Rajarhat sub-stations

In last OCC, WBSETCL updated the latest status as follows:

SI. No.	Name of the transmission line	Completion schedule
1.	2x315MVA, 400/220kV Alipurduar sub-station	
a.	Alipurduar (POWERGRID) – Alipurduar (WBSETCL) 220kV D/c ( <i>Twin moose</i> )	Dec, 2017
2.	2x500MVA, 400/220kV Rajarhat	
a.	Rajarhat-N. Town-3 (WBSETCL) 220 kV D/C line	Matching
b.	Rajarhat-N. Town-2 (WBSETCL) 220 kV D/C line	June, 2018
C.	Rajarhat- Barasat (WBSETCL) 220 kV D/C line	June, 2018

### WBSETCL may update.

### Item no. C.17: Erection and commissioning of 02 nos. of 220 kV line bays at KBUNL

Despite of several requests and reminders, KBUNL is not taking up this work seriously and it appears that the initiatives of KBUNL for construction of bay, which is essential for making available second circuit with Samastipur(New) and Motipur are far from satisfactory and the work is yet to start. Presently 220 KV KBUNL- Samastipur (new) (D/C) & 220 KV KBUNL - Motipur (D/C) tr. lines have only one 220 KV bays each at KBUNL end since long & due to this one circuit each from KBUNL to Samastipur (new) & KBUNL to Motipur remain unutilised. Due to unavailability of these bays at KBUNL end, BSPTCL is facing difficulties for synchronising 220 KV line at KBUNL and also unable to shift loading of Biharsharif(PG)-Begusarai D/C T/L on MTPS for off loading of Biharsharif(PG) ICTs and in case of any contingency occurs at DMTCL(D)-Motipur D/C T/L, MTPS-Motipur S/C T/L also tripped at overloading. It is evident that the transmission infrastructure developed by BSPTCL in North Bihar could not be fully utilized causing limitations in power flow as well as power interruption.

The unavailability of bays at KBUNL is affecting the evacuation of power from KBUNL (Generating Station 2\*110 MW+2\*195MW). So, keeping these lines in loop at KBUNL will enhance the quality, reliability and stability of system.

KBUNL may begin the construction and complete commissioning of 2<sup>nd</sup> bay in minimum possible time in order to avoid crisis arisen due to unforeseen outage of Biharsharif(PG) and DMTCL(Darbhanga).

As such target dates for the start and completion of the above works may kindly be got ensured from KBUNL.

In 140<sup>th</sup> OCC, KBUNL informed that tender has been floated and the work will be awarded in December 2017. The work will be completed by March 2018.

### KBUNL may update.

### Item no. C.18: Update on status of telemetry

CERC vide order dated 28.02.2016 on Petition No. 007/SN/2014 directed NLDC and respective RLDCs to update the status of telemetry every month at their respective websites and take up the issue of persistent non-availability of data from Generating Stations/substations at RPC meetings for appropriate action.

### **ERLDC** may present.

### a) Frequent failure of JITPL data to ERLDC:

In 36<sup>th</sup> TCC, Powergrid agreed to allow JITPL to shift their PLCC modem from Bolangir S/s within a week.

JITPL informed that they will shift the modem within a week and they will commission the communication system in another 10 days subject to availability of OEM (ABB) engineers.

TCC advised JITPL to shift the modem as decided and update the status in forthcoming OCC meeting scheduled to be held on 21<sup>st</sup> September 2017.

In 137<sup>th</sup> OCC, JITPL informed that they have shifted the PLCC modem from Bolangir to Angul and they will commission the communication system by 15<sup>th</sup> October 2017.

In 140<sup>th</sup> OCC, ERLDC informed that JITPL data through PLCC is not yet restored.

### JITPL may update.

### Item no. C.19: Updating of GT and ICT Tap position of all EHV transformers

All the generation, transmission and distribution utilities have been requested to go through **Annexure-C19** related to last updated information related to GT/ICT/ATRs available at ERLDC and update the capacity, number, tap details, make (Company name) and other information including addition of new transformers, wherever felt necessary.

OCC advised all the constituents to go through the Annexure and send the updated information to erldcprotection@gmail.com.

### Members may update.

### Item no. C.20: Checklist for submission of updated data for Protection Database

The network data in Protection Database needs to be updated on regular basis on account of commissioning of new elements in the CTU as well as STU networks. Accordingly, a checklist has been prepared which is enclosed in **Annexure-C20**.

All the constituents are requested to submit the checklist on monthly bases in every OCC/PCC meetings.

In 139<sup>th</sup> OCC, all the constituents were advised to submit the data to ERPC vide mail (mserpc-power@nic.in) as per the checklist for last three months.

OCC advised all the constituents to submit the data to ERPC vide mail (mserpc-power@nic.in) as per the checklist for last three months.

### Constituents may update.

### Item no. C.21: Transfer capability determination by the states -- Agenda by NPC

In order to ensure, safe and secure operation of the grid, the states should carry out the power system study for operational planning and power transfer capability through their respective transmission links with the rest of the grid.

It was decided in the NPC meeting that to begin with, power system study for assessment of operational limits / power transfer capability for each state will be done by the concerned RLDC in association with concerned SLDC. Monthly TTC /ATC will be uploaded by the SLDCs at their respective websites and also communicated to concerned RLDC & NLDC subsequently.

ATC/TTC declared by states for the month of January-2018 is given below:

SI No	State/Utility	TTC import(MW)	RM(MW)	ATC (Import) MW
1	BSPTCL			
2	JUSNL			
3	DVC	828	52	776
4	OPTCL	1773	99	1674
5	WBSETCL	4610	300	4310
6	Sikkim			

### Members may update.

# Item no. C.22: Time correction of SEMs in Eastern Region – Replacement of heavily drifted SEMs

The issue was discussed in 35th TCC/ERPC meetings and it was felt that the meters with severe drift greater than 10 min need to be replaced first and if replacement is done with Genus then readings are to be collected manually using Laptop till interfacing with AMR is completed. 35th ERPC advised Powergrid to replace the 10% of the heavily drifted SEMs with new Genus make meters in Phase-I. Subsequently drifted meter replacement work of Phase –I for 24 meters have been completed.

As per decision taken in 134<sup>th</sup> OCC meeting, another 10% heavily drifted meter list was prepared by ERLDC and given to Powergrid for replacement. In 140<sup>th</sup> OCC it was informed that all the Phase-II meters have been replaced except Kharagpur. Since issue of integration of Genus meter is already resolved, It was also decided that list of meters to be replaced in next phase may be prepared.

Accordingly List of drifted meters to be replaced in Phase-III is placed below:

	List of drifted meter	rs to be replaced in	Phase-III	
SNO	LOCATION	METER SNO	FEEDER NAME	Region
1	JEERAT(WB)	NP-6445-A	400 KV JEERAT (WBSETCL) - BERHAMPORE(PG)	ER-II
2	JEERAT(WB)	NP-6446-A	400 KV JEERAT (WBSETCL) - SUBHASGRAM	ER-II
3	RANCHI(PG)	NP-7853-A	400 KV RAGHUNATHPUR 1	ER-I
4	RANCHI(PG)	NP-7871-A	400 KV RAGHUNATHPUR 2	ER-I
5	ALIPURDUAR(PG)	NR-3716-A	400 KV POLE-3 MAIN BAY-AGRA(NR)	ER-II
6	ALIPURDUAR(PG)	NR-3718-A	400 KV POLE-3 TIE BAY AGRA(NR)	ER-II
7	NEW MELLI(PG)	NR-4620-A	220 KV JORETHANG(JLHEP)-1	ER-II
8	NEW MELLI(PG)	NR-4621-A	220 KV JORETHANG(JLHEP)-2	ER-II
9	TEESTA-III	NR-3714-A	400 KV SIDE OF TEEST-III HEP GT-1	ER-II
10	TEESTA-III	NR-3715-A	400 KV SIDE OF TEEST-III HEP GT-2	ER-II
11	TEESTA-III	NR-4450-A	400 KV SIDE OF TEEST-III HEP GT-3	ER-II
12	TEESTA-III	NR-3720-A	400 KV SIDE OF TEEST-III HEP GT-4	ER-II
13	TEESTA-III	NR-4623-A	400 KV SIDE OF TEEST-III HEP GT-5	ER-II
14	TEESTA-III	NR-3719-A	400 KV SIDE OF TEEST-III HEP GT-6	ER-II
15	TEESTA-III	NR-4456-A	400 KV TEESTA-III - DICKCHU (MAIN)	ER-II
16	TEESTA-III	NR-4618-A	400 KV TEESTA-III - DICKCHU (CHECK)	ER-II
17	TEESTA-III	NR-4454-A	400 KV TEESTA-III - RANGPO (MAIN)	ER-II
18	TEESTA-III	NR-4453-A	400 KV TEESTA-III - RANGPO (CHECK)	ER-II
19	JINDAL (GRIDCO)	NP-6502-A	220KV JAMSHEDPUR (DVC)	ODHISA PROJECT
20	JAMSHEDPUR (DVC)	NP-6010-B	220 KV JINDAL	ER-I
21	GANGTOK(PG)	NP-6026-A	132KV CHUZACHEN(GATI)	ER-II
22	RANGPO(PG)	NP-7958-A	132 KV CHUZACHEN (GATI)	ER-II

### Powergrid may update.

### Item no. C.23: Meter related Issues-ERLDC

Due to the meter related issues of following locations energy accounting and its validation is being affected.

Issue	Location	Meter No	Line	Responsibility	Problem Since	Present Status
Non receipt of Data	1. NPGC	NP-1282-A NP-1287-A	132 KV Rihand & Sonnagar	BSPTCL	More than 3 month	Not Received. Status is same
Installat ion of Check/S	1.Subhashgram(WB ) 2. New Town(WB)		220 KV Subhasgram(PG) D/C 220 KV Subhasgram(PG)	WBSETCL/PG CIL WBSETCL/PG	Charging of Line Charging of Line	As informed by PGCIL, Meter is available at
tandby meter	3. Bantala(WB)		S/C  220 KV Subhasgram(PG)  S/C	CIL WBSETCL/PG CIL	Charging of Line	Subashgram and the same to be collected by WBSETCL and to be put
	4. EM Bypass(CESC)		220 KV Subhasgram(PG) D/C	WBSETCL/PG CIL	Charging of Line	into service.  Meter already connected but time synchronisation yet to be done. SEM data is not received by ERLDC

In 140<sup>th</sup> OCC , BSPTCL was advised to communicate the problem of downloading the data of NPGC to Powergrid. WBSETCL was also advised to install the meters at the earliest. However NPGC end data is not received by ERLDC. Meter at WBSETCL/CESC end for New Town, Bantala and Subhasgram is yet to be installed.

### PGCIL/BSPTCL/WBSETCL/may please further update the status.

### Item no. C.24: Less recording by Joda OPTCL end meter

Meter No NP-5937-A installed at Joda end of 220 Ramchandarpur is recording 10 % to 15 % Less as compared to Ramchandarpur end since 06.12.2017. Subsequently ERLDC vide mail dated 14.12.17 (with a copy to PGCIL) requested OPTCL to check CT/PT connection to the said

meter. However the problem is still persisting and GRIDCO accounting is done with Ramchandarpur end meter.

### **OPTCL/PGCIL** may please further update.

### Item no. C.25: Mock Black start exercises in Eastern Region – ERLDC

### i) The status of black start exercises

The tentative schedule of black-start exercises for F.Y 2017-18 is as follows:

SI no	Name of Hydro Station	Schedule	Tentative Date	Schedule	Tentative Date
		Test-I	•	Test-II	•
1	U.Kolab	Last week of May, 2017	30 <sup>th</sup> May 2017	Last Week of January2018	January 2018
2	Maithon	1stweek of June 2017	Completed or 04.04.17	1stWeek of February2018	
3	Rengali	2ndweek of June 2017	Done or 29.06.2017	Last week of November 2017	Done 30 <sup>th</sup> November 2017
4	U. Indarvati	3rdweek ofJune 2017	November 2017	2ndweek of February2018	January 2018
5	Subarnarekha	1stweek of October 2017	Done on 14 <sup>tr</sup> October 2017	1stweek of January2018	
6	Balimela	3rdweek of October 2017	November 2017	1stweek of March 2018	January 2018
7	Teesta-V	2ndweek of Nov 2017		Last week of February2018	Last week of December 2017
8	Chuzachen	Last Week of May2017	May, 2017	January2018	
9	Burla	Last Week of June 2017	Dec, 2017	Last week of February2018	Feb. 2018
10	TLDP-III	1stWeek of June 2017	After 12the Dec 2017.	2ndWeek of January2018	
11	TLDP-IV	Last Week of June 2017	After Mansoon	1stWeek of February2018	
12	Teesta-III		December 2017		6 <sup>th</sup> January 2018

OHPC informed that the black start exercise of unit-3 of Upper Kolab P.H. has been successfully completed on 09.01.2018 at 16:07 Hrs.

The black start exercise of Upper Indravati P.H. which was scheduled to be carried out on 09.01.2018 at 11:00Hrs could not be carried out due to transmission line problem and will be performed later.

### Members may update.

### ii) Testing of DG sets meant for Black start

Test run report of DG sets for blackstart has been received only from Odisha hydro units. The test run reports of other machines may be sent to erldc.cal@gmail.com and erldcoutage@gmail.com.

### Constituents may kindly ensure compliance.

### Item no. C.26: Schedule for reactive capability tests

The following was status of regarding reactive capability testing:

- a. Adhunik TPS(both units) -Yet to be confirmed by Adhunik
- b. JITPL(both units) After the emergent inspection of OEM(BHEL)
- c. Barh TPS November 2017
- d. Raghunatpur (both units) by December 2017
- e. GMR (Three units)- January 2018

### Members may update.

### Item no. C.27: Installation of PMUs in Eastern Region under URTDSM project

LOA for installation of PMUs in Eastern Region under URTDSM project was awarded to M/s Alstom on 15th January 2014. The contract has to be completed in all respect within 24 months from the award. The status of implementation may be informed since PMU data is very much important to real time shift operator for analyzing the security of the grid.

The updated status as furnished in 140<sup>th</sup> OCC by Powergrid is given at **Annexure-C.27**.

Powergrid vide mail dated 8<sup>th</sup> January 2018 informed that they are facing difficulty in installation of PMUs at following locations:

- 1. MONNET: There is no response from Monnet site regarding readiness of site for Installation of PMU. Material delivered at site in the month of August 2017.
- 2. IBEUL: Material delivered at site in the month of August. Accordingly team was deployed for installation. But Due to non-readiness at site the team could not work and has to returned back. Till now permission has not been granted for PMU installation.
- 3. JITPL: Material delivered at site in the month of August. Team was deployed for PMU installation. Due to space constraint the installation could not be done.

### POWERGRID may update the status.

### Item no. C.28: Non Payment of dues--Powergrid-Odisha

- A. **JITPL**: Rs. 1.05 Crore from M/s JITPL (Rs. 52.92 Crore towards bay maintenance + Rs. 52.38 Lakh towards interest charges)
- B. **Ind-Bharath Energy(Utkal) Ltd(IBEUL):** Rs.59.16746 Lakh is due from M/s Ind-Bharath (Utkal) Energy Limited towards Bay maintenance and Interest charges.

### JITPL and IBEUL may update.

### PART D:: OPERATIONAL PLANNING

### Item no. D.1: Anticipated power supply position during February'18

The abstract of peak demand (MW) vis-à-vis availability and energy requirement vis-à-vis availability (MU) for the month of February'18 were prepared by ERPC Secretariat on the basis of Provisional LGBR for 2015-16 and feedback of constituents, keeping in view that the units are available for generation and expected load growth etc. is at **Annexure-D.1**.

ERPC Secretariat is not receiving the actual figures of previous month power supply position in time. All the constituents should furnish the information to ERPC Secretariat by 10<sup>th</sup> of every month.

### Members may confirm.

# Item no. D.2: Shutdown proposal of transmission lines and generating units for the month of February'18

Members may finalize the Shutdown proposals of transmission lines and generating stations for the month of February'18 as placed at **Annexure-D.2.1**.

### ERLDC may place the transmission line shutdown. Members may confirm.

### 1. Deemed availability for insulator replacement works—Powergrid

Powergrid vide letter dated 29<sup>th</sup> December 2017 requested for considering deemed availability during the shutdown period availed for insulator replacement. Details are enclosed at **Annexure-D2.2.** 

### Members may approve.

### Item no. D.3: Prolonged outage of Power System elements in Eastern Region

### (i) Thermal Generating units:

Sr. No	Generating Station	Unit Number	Capacity( MW)	Reasons For Ouatge	Outage Date
1	ADHUNIK	2	270	GENERATOR VIBRATION	7-Sep-17
2	JITPL	1	600	BOTTAM ASH EVACUATION PROBLEM	30-Dec-17
3	GMR	1	350	COAL SHORTAGE	9-Dec-17
4	VEDANTA	2	600	MAINTENANCE	28-Jun-17
5	МЕЛА В	8	500	VIBRATION PROBLEM IN BEARING , TURBINE BLADE DAMAGE	7-Aug-17
6	RAGHUNATHP UR	2	600	COAL SHORTAGE	27-Dec-17
7	МЕЛА	5	250	PROBLEM IS IN BARRING GEAR	22-Sep-17
8	MEJIA B	7	500	BTL	2-Jan-18
9	BOKARO B	3	210	COAL SHORTAGE	31-Dec-17
10	SAGARDIGHI	1	300	FLAME FAILURE	27-Dec-17
11	DPL	8	250	250 BOILER TUBE LEAKAGE	
12	KOLAGHAT	3	210	210 BOILER TUBE LEAKAGE	
13	KOLAGHAT	3	210	MAINTENANCE	22-Feb-17
14	KOLAGHAT	2	210	DYSND. FOR POLLUTION	31-Dec-17

				CONTROL	
15	KOLAGHAT	6	210	STATOR EARTH FAULT	11-Jun-17

### (ii) Hydro Generating units:

Sr. No	Generating Station	UNIT NO	CAP(MW)	REASONS FOR OUTAGE	OUTAGE DATE
1	BURLA	5	37.5	R & M WORK	25.10.2016
2	BURLA	6	37.5	R & M WORK	16.10.2015
3	BURLA	3	32	AMC WORK	02.01.2018
4	CHIPLIMA	3	24	R & M WORK	15.10.2015
5	BALIMELA	1	60	R & M WORK	05.08.2016
6	BALIMELA	2	60	R & M WORK	20.11.2017
7	BALIMELA	7	75	Governor & Guide vane problem	12.10.2017
8	U.KOLAB	2	80	Repair of MIV & Draft tube gate leakage	28.05.2017
9	RENGALI	5	50	Hoist gate problem	21.03.2017

### (iii) Transmission elements

Transmission Element / ICT	Agency	Outage Date	Reasons for Outage
220 KV BALIMELA - U' SILERU	OPTCL / APSEB	27.04.15	LINE IDLE CHARGED FROM UPPER SILERU END AT 12:42 HRS OF 25.01.17
400KV MOTIHARI-BARH-I & II	DMTCL	14.08.17	24 NO OF TOWERS IN GANDAK RIVER WHERE WATER LEVEL IS HIGH
220 KV BUDHIPADAR KORBA- I	POWERGRID	1.11.17	MULTI CKT TOWER ERECTION AND DIVERSION WORK FROM LOC 29 to 40
400KV TALA -BINAGURI -I	POWERGRID/BHU TAN	29.12.17	S/D AVAILED BY BHUTAN

(Reported as per Clause 5.2(e) of IEGC)

### Members may update.

### Item no. D.4: Status of commissioning of generating station and transmission elements

**New generating units:** 

٦	S.No. Power Plant		Plant Size Expected da	

### **New transmission elements:**

SI No.	Name of Element	Expected date
1	400kV Rajarhat-Purnea D/C (with LILO of one circuit each at	
	Farakka and Gokarno)	
2	Augmentation of 400kV Farakka-Malda D/C with HTLS conductor	
3	400kV Ind-Bharath-Jharsuguda D/C	
4	400kV Talcher-Bramhapur-Gazuwaka D/C	
5	400kv Talcher-Rourkella(2 <sup>nd</sup> D/C-Quad)	
6	400kV Sterlite-Jharsuguda D/C	
7	765kv Anugul-Srikakulum D/C	
8	400kV Sasaram-Daltonganj D/C &Daltonganj S/Stn	
9	400 kV Ranchi-Raghunathpur D/C	
10	220 kV TLDP-IV – NJP ckt-2	
11	220 kV Bidhansai-Cuttack D/C	
12	220kV Gola- Ranchi	

### Members may update.

### PART E:: ITEMS FOR INFORMATION

### Item No. E.1: Swapping Scheme of 765KV Jharsuguda- Dharamjaygarh lines 1&2 with 3&4

Powergrid vide mail dated 12-01-2018 informed that 765KV Jharsuguda-Dharamjaygarh Circuit#3 and circuit#4 is ready to charge from Jharsuguda end. 765 KV Jharsuguda-Dharamjaygarh Circuit#1 and circuit#2 is already in operation. Ckt#3 and #4 need to cross existing ckt#1 and ckt#2 for termination at Jharsuguda switch yard. To avoid the crossing of lines ckt#1 and ckt#2 swapped with Circuit #3 and #4.

### Line details:

Lines	Original	Line	length after s	Bay swapping		
	Length(KM)	Old	New	Total	Old Bay	New Bay
		portion	Portion	Length(KM)		
Circuit #1	151.55	112.869	39.192	152.061	715	721
Circuit#2	151.55	112.869	39.192	152.061	718	724

<sup>\*</sup> Note: There is no interchange of bays at Dharamjaygarh end

### Members may note.

### Item No. E.2: Swapping Scheme of 765KV Jharsuguda - Angul lines 1&2 with 3&4

Powergrid vide mail dated 12-01-2018 informed that 765 KV Jharsuguda-Angul lines 1&2 is already in operation.765KV Jharsuguda-Angul lines 3 & 4 are in the last stage of completion. Circuit #3 & #4 needs to be crossed over existing ckt#1 & #2 for to termination at Jharsuguda switchyard. Hence to avoid crossing of 765 KV lines over another, ckt#1 and ckt#2 swapped with Circuit #3 and #4.

### Line details:

Lines	Original	Line le	ength after swa	apping	Bay swapping		
	Length(KM)	Old	New	Total	Old	New	
		portion(KM)	Portion(KM)	Length(KM)	Bay	Bay	
Circuit #1	270.856	270.554	0.374	270.928	710	716	
Circuit#2	276.856	276.554	0.374	276.928	707	713	

### Members may note.

### Item No. E.3: 2. Anti-theft Charging of 765KV Sundargarh-Dharamjaygarh ckt#3 & ckt#4.

Powergrid vide mail dated 12-01-2018 informed that circuit 3 and 4 is ready for Odisha portion(43.941KM) only and WR portion under construction. They are charging the line from Jharsuguda end to avoid theft of conductor.

### Members may note.

### Item No. E.4: Restricted Governor /Free Governor Mode Operation of generators in ER

CERC vide their letter dated 05-06-2017 desired to know the present status of RGMO/FGMO response of all eligible thermal and hydro units. Accordingly ERLDC vide letter no.ERLDC/SS/FGMO/2017 dated 07-06-17 requested all concerned power stations and SLDCs to provide updated status of FGMO/ RGMO of units under their control.

The latest status of the RGMO/FGMO of ER generators is enclosed in Annexure-E4.

### Members may note.

# Item No. E.5: Preparation of crisis management plan for Cyber Security in Power Sector in line with CERT-IN.

The activity of the preparation of Crisis Management Plan for countering the cyber attacks and its implementation including the Mock Drills, audits etc. is being monitored by CEA regularly in line with crisis management plant of Ministry of Power. Power Utilities (including generation, transmission & distribution utilities) of eastern region are to furnish regularly the updated status to on the same to Chief Engineer, Distribution Planning & Development Division, CEA.

NTPC communicated their activity of the preparation of Crisis Management Plan for countering the cyber attacks vide letter dated 2<sup>nd</sup> August, 2013.

In 113<sup>th</sup> OCC, Member Secretary informed that during interaction with consultants of Grid Study Committee, NLDC agreed that they will plan for conducting workshops on crisis management plan for Cyber Security and few workshops will also be held in Eastern Region.

CESC vide letter dated 22.08.15 had furnished their status of the preparation of Crisis Management Plan (CMP) for Cyber attacks in their system.

### Members may note.

### Item No. E.6: Certification through BIS as per IS 18001:2007 to all generating/ transmission units.

In 84<sup>th</sup> OCC meeting all constituents were requested to interact with BIS with intimation to ERPC and get certified as per CEA direction.

As per the information received from the constituents the following generators certified with IS 18001:

- All NTPC stations in Eastern Region
- Teesta, NHPC
- All OHPC generating units
- All CESC generating units
- All units of WBPDCL
- DGPC units

### Members may note.

# Item No. E.7: Status of Disturbance Recorder, Stand alone Event Logger and Time Synchronization equipment.

The status of DR/EL and GPS as updated in previous OCCs is enclosed at Annexure-E.7.

Constituents are also requested to furnish their list of new DR/EL which are not included in the list.

Teesta Urja Limited vide letter dated 8<sup>th</sup> September 2017 informed that Disturbance Recorder, Stand alone Event Logger and Time Synchronization equipments are available at Teesta III HEP.

### Members may note.

# Item No. E.8: Status of Emergency Restoration System (ERS Towers) for Eastern Region constituents

CEA vide letter dated 21.07.2017 requested to send the status of state-wise availability of ERS towers and requirement of ERS towers.

In 136<sup>th</sup> OCC, MS, ERPC informed that CEA vide letter dated 21.07.2017 has sought the latest status on ERS. Therefore, OCC advised all constituents to send the updated status to ERPC secretariat vide mail (mserpc-power@nic.in).

Latest status is enclosed at **Annexure- E.8**.

In 138<sup>th</sup> OCC, WBSETCL informed that they are having total 10 ERS towers, 5 at Arambagh and 5 at Gokharno.

In 139<sup>th</sup> OCC, JUSNL informed that they are having eight 220/132kV ERS towers at following locations:

- Hatia 3 nos
- Ranchi 2 nos
- Dumka 3 nos

### Members may note.

### Item No. E.9: Status of 1<sup>st</sup> Third Party Protection Audit:

The compliance status of 1<sup>st</sup> Third Party Protection Audit observations is as follows:

Name of Constituents	Total Observations	Complied	% of Compliance
Powergrid	54	37	68.52
NTPC	16	14	87.50
NHPC	1	1	100.00
DVC	40	26	65.00
WB	68	27	39.71
Odisha	59	38	64.41
JUSNL	34	21	61.76
BSPTCL	16	5	31.25
IPP (GMR, Sterlite and MPL)	5	5	100.00

The substation wise status of compliance are available at ERPC website (Observations include PLCC rectification/activation which needs a comprehensive plan).

In 118<sup>th</sup> OCC, all the constituents were advised to comply the pending observations at the earliest. All the STUs informed that most of the observations are related to funding from PSDF. DPRs have been submitted to PSDF committee.

OCC advised all specially JUSNL and BSPTCL to send the revised DPRs at the earliest after clarifying the queries if any.

Members may comply.

Item No. E.10: Additional agenda

\*\*\*\*\*

### <u>Annexure</u>

Name of the Element	Pov	ver Flow
Name of the Element	Before	After
	Bus I & III (Maithon A)	
400 KV Maithon-Mejia I,II	27 each (Mejia)	162 each (Maithon)
400 KV Maithon-Kahalgaon II	69 (Maithon)	189 (Maithon)
400 KV Maithon-Jamshedpur	168 (Jamshedpur)	108 (Maithon)
400 KV Maithon-Gaya D/c	228 each (Gaya)	126 each (Gaya)
2*500 MVA ICT at Maithon	374	248
	Bus II & IV (Maithon B)	
400 KV Maithon-MPL D/c	360 each (Maithon)	314 each (Maithon)
400 KV Maithon-Raghunathpur	194 (Maithon)	70 (Maithon)
400 KV Maithon-Ranchi	66 (Ranchi)	112 (Ranchi)
400 KV Maithon-Durgapur D/c	36 (Maithon)	112 each (Durgapur)
400 KV Maithon-Kahalgaon I	69 (Maithon)	22 (Kahalgaon)
400 KV Maithon-Mejia III	22 (Mejia)	342 (Mejia)

С	hanges in 220 KV Network	
220 KV Maithon-Dhanbad D/c	134 each (Dhanbad)	125 each (Dhanbad)
220 KV Maithon-Kalyaneshwari D/c	39 each (Kalyaneshwari)	10 each (Maithon)
220 KV Mejia-Kalyaneshwari T/c	86 each (Kalyaneshwari)	110 each (Kalyaneshwari)
220 KV Kalyaneshwari-CTPS A	65 (CTPS A)	60 (CTPS A)
220 KV Dhanbad-CTPS B	41 each (CTPS B)	30 each (CTPS B)
220 KV CTPS A-CTPS B	195 each (CTPS A)	200 each (CTPS A)

Note: Direction of power flow is towards S/s mentioned in parenthesis

		Bus I	& III	Bus II & IV		
Voltago Changos		Bus I	Bus III	Bus II	Bus IV	
Voltage Changes	Before Splitting	415 KV	417 KV	412 KV	414 KV	
	After Splitting	414 KV	411 KV	419 KV	416 KV	

Minor voltage difference between connected buses is due to measurement errors

# VDI of Selected 765 kV & 400 kV in Eastern Region in the month of December - 2017

नई र	रांची / Ranchi	New	जमशे	जमशेदपुर / Jamshedpur		मुजफ्फरपुर / Muzaffarpur		
MAX	MIN	VDI (% of Time)	MAX	MIN	VDI (% of Time)	MAX	MIN	VDI (% of Time)
799	767	0.00	429	410	53.98	417	389	0.00

बिहार	बिहार शरीफ / Bihar Sariff			बिनागुरी / Binaguri			जीरत / Jeerat			
MAX	MIN	VDI (% of Time)	MAX	MIN	VDI (% of Time)	MAX	MIN	VDI (% of Time)		
421	400	2.50	426	399	26.56	431	394	37.94		

राउ	राउरकेला / Rourkela			जयपोर / Jeypore			कोडरमा / Koderma		
MAX	MIN	VDI (% of Time)	MAX	MIN	VDI (% of Time)	MAX	MIN	VDI (% of Time)	
422	407	1.97	426	380	0.23	423	409	12.12	

1	मैथन / Maithon			तीस्ता / Teest	a	रांगपो / Rangpo		
MAX	MIN	VDI (% of Time)	MAX	MIN	VDI (% of Time)	MAX	MIN	VDI (% of Time)
421	407	0.45	424	393	9.25	422	389	1.51

# Reports on real time telemetry failure of Eastern Region on 06<sup>th</sup> December 2017

### **Overview:**

On 06<sup>th</sup> December 2017 at 17:26 hours, there was failure of real time SCADA data of 17 nos Central Sector station to ERLDC due to communication failure between Malda – Farakka OPGW link. The real time data restored at 09:37 Hours of 07<sup>th</sup> December 2017.

### **Background:**

Real time SCADA data and voice connectivity of 17 no of Central sector station (geographically located in North Bengal and Sikkim area) with ERLDC is established through Malda, Farrakka. Communications link between Malda - Farakka OPGW was not healthy. On 06<sup>th</sup> December 2017 at 17:26 hours, there was some problem in Malda Farakka OPGW link causing disruption in data and voice communication of Central sector stations (located in North Bengal and Sikkim area) with ERLDC. At 09:37 Hours of 07<sup>th</sup> December 2017, maintenance team reached at site and restored the communication. Real time data and voice of these 17 no of stations were unavailable for around 16 hours and 23 minutes (as shown in figure 1)




Fig 1: Total No of central sector stations reporting to ERLDC dated 06th December, 2017.

### Data Availability Tabular Display of Central Sector Stations in Eastern Region

JEYPORE	TALCHER HVDC	INDRAVATI	PATNA	RENGALI
JITPL	TALCHER	ROURKELA	TALA HEP	JAMSHEDPUR
MAITHON	RANCHI	DURGAPUR	FARAKKA STPS	KAHALGAON STPS
BIHARSHARIFF(PG)	BAHARAMPUR	LALMATIA	GAZUAWAKA	MALDA(PG)
DALKHOLA(PG)	PURNEA(PG) 220KV	SILIGURI 220(PG)	BIRPARA(PG)	CHUKHA HEP
BINAGURI 400	RANGIT HEP	PURNEA 400	SASARAM PG 400KV	KALABADIA PG
SUBHASGRAM (PG)	TEESTA HEP	MUZAFFARPUR PG	GANGTOK	ARRAH PG
APNRL	STERLITE	MTHRB	BARH STPS	GAYA PG
FARAKKA SAS(III)	BOLANGIR PG	KEONJHOR PG	PANDIABILI PG	ANGUL PG
JHARSUGUDA AIS PG	CHUZACHEN HEP	BANKA PG	IBEUL	LAKHISARAI PG
CHAIBASA PG	SASARAM 765	NABINAGAR TPS	BHVDC	NEW RANCHI PG
MELLI NEW PG	KISHANGANJ PG	RANGPO PG	JORETHANG HEP	CHANDWA PG
KBUNL II	ALIPURDUAR HVDC	TEESTA III HEP	DARBHANGA DMTCL	DIKCHU HEP
DSTPP	MOTIHARI DMTCL			

Fig 2: Data availability display as on 20:01 Hrs 06-12-2017 (Green: Available, Red: Unavailable)

### **Findings & Conclusion:**

There was communication link problem between Malda – Farakka OPGW section (shown in fig 3 below) causing the above said data interruption. The data & voice communication restored after shifting of fibre core to healthy one as informed by POWERGRID ERTS – 2 ULDC team.




Fig 3: Communication link (OPGW) diagram between North Bengal and Sikkim with ERLDC

Availability of path redundancy of Malda – Farakka communication link could have prevented such unwanted disruption in real time voice and telemetry communication. Non availability of stand by channel to backup ERLDC located NLDC New Delhi, which is required as per Central Electricity Regulatory Commission (Communication System for inter-State transmission of electricity) Regulations, 2017, is getting prompted as matter of great concerns which need immediate attention of all Eastern Regional utility and communication links provider i.e. POWERGRID ULDC.

The alternate protection path could be achieved after installation of OPGW communication link between Purnea 400 kV to Biharshariff 400 kV. This link is owned by M/s East North Interconnection Company Limited (a subsidiary of Sterlite Power Transmission Limited).

The above failure impact could be mitigated with the help of followings measure:-

- a. Provision of laying OPGW communication link between Purnea 400 kV to Biharshariff 400 kV could be explored and implemented so that alternate protection path would be available for Malda Farakka communication link data & voice transfer in case of such failure.
- b. The standby / backup communication links to backup ERLDC located at New Delhi for central sectors stations are yet to be provided by POWERGRID. The availability of the standby links could have mitigated the failure of all central sector station real time SCADA data at ERLDC.

We all know that the importance of real time SCADA data & voice availability to the real time operators in making decision for ensuring integrated operation of the power system, Reliability, Security and Economy in Power System Operation in Eastern Region.

:: xx ::

# Reports on real time telemetry failure of Eastern Region on 14<sup>th</sup> December 2017

### Overview:

On 14<sup>th</sup> December 2017 at 12:52 hours, there was almost complete outage of real time SCADA telemetry and voice connectivity of Eastern Region due to communication failure. The real time data partially restored at 14:33 Hours and completely restored at 15:28 Hours of 14<sup>th</sup> December 2017.

### Background:

Real time SCADA data and voice connectivity of PMUs installed in Eastern Region, central sector RTU/SAS, all SLDCs, NLDC with ERLDC is established through Jeerat & Kasba. There are two communications path available from Jeerat to Kasba mainly one direct Jeerat Kasba OPGW & another Jeerat – Subhashgram – Kasba OPGW (shown in fig 1). On 14<sup>th</sup> December 2017 at 12:52 hours, there was almost complete outage of real time SCADA telemetry and voice connectivity of Eastern Region due to communication failure.

The real time SCADA data was interrupted due to fibre issue between Jeerat – Kasba section.




Fig 1: Communication diagram between ERLDC and Jeerat.

Real time data of entire Central sector station (as shown in fig 2) and all stations under state sector jurisdiction (except West Bengal) (as shown in fig 3) and other neighbor region, VOIP connectivity of ERLDC, data exchange with Back up ERLDC located at New Delhi, PMU data exchange of ER WAMS pilot project as well as of URTDSM project got disrupted due to the incident. Data exchange between Main NLDC & Main NRLDC located New Delhi and Back up NLDC & NRLDC, Kolkata also got interrupted.




Fig 2: Total Nos of central sector stations reporting to ERLDC dated 14<sup>th</sup> December, 2017.




Fig 3: Total nos of station's (State sector) data available ERLDC dated 14 December, 2017.

### Findings & Conclusion:

There was planned activity going on between Kasba - Jeerat OPGW section (shown in fig 1 above) in co-ordination with WBSETCL & POWERGRID. Alternate protection path via Subhasgram was configured but not worked at the time of the event. ERLDC was not aware about the ongoing activity.

The same could be avoided with the help of followings:-

- a. Protection path was configured as claimed by POWERGRID but not tested. The same could have been tested taken due confidence of ERLDC.
- b. The standby / backup ICCP communication links to backup ERLDC located at New Delhi are yet to be provided by POWERGRID. The availability of the standby links could have mitigated the failure of all state sector (Except West Bengal) real time SCADA data at ERLDC.
- c. Similarly, the standby / backup communication links to backup ERLDC located at New Delhi for central sectors stations are yet to be provided by POWERGRID. The availability of the standby links could have mitigated the failure of all central sector station real time SCADA data at ERLDC.

We all know that the importance of real time SCADA data & voice availability to the real time operators in making decision for ensuring integrated operation of the power system, Reliability, Security and Economy in Power System Operation in Eastern Region.

To prevent such unwanted disruption in real time telemetry and Voice communication, standby/backup channel has to be implemented by POWERGRID at the earliest. Both the channel i.e. main and stand by channel has to be kept in healthy state. Drills have to be conducted at regular interval for checking healthiness of both the channels. Measures have to be taken and implemented to standardize the regional communication system as per Central Electricity Regulatory Commission (Communication System for inter-State transmission of electricity) Regulations, 2017 which is enforced since 01-07-2017 as per gazette notification dated 15-05-2017.

## PPA details for the year 2017-18 to 2019-20

			2017-18			2018-19			2019-20	
		Share/Contracted power (in MW)		Variable charges (Rs/kwh)	Share/Contracted power (in MW)	Fixed Charges (Rs/kwh)	Variable charges (Rs/kwh)	Share/Contracted power (in MW)	Fixed Charges (Rs/kwh)	Variable charges (Rs/kwh)
	1. Hydro Generation	power (in iviv)	(R3/RWII)	(KS/KWH)	power (iii www)	(K37 KWH)	(NS/NWII)	power (iii ivivv)	(R3/RWII)	(KS/ KWH)
(a)	Own generation									
i	Power station I									
ii.	Power station II									
iii.	Power station III									
iv.	Power station IV									
(b)	CGS generation									
i.	Power station I									
ii.	Power station II									
iii.	Power station III									
iv.	Power station IV									
(c)	IPP's generation									
i.	Power station I									
ii.	Power station II									
iii.	Power station III									
iv.	Power station IV									
	. Thermal Generation (Coal/Gas/Nuclear)									
(a)	Own generation									
i.	Power station I									
ii.	Power station II									
iii.	Power station III									
iv.	Power station IV									
IV.										
/h\										
(b)	CGS generation									
l. 	Power station I									
ii.	Power station II									
iii.	Power station III									
iv.	Power station IV									

(c)	IPP`s generation					
i.	Power station I					
ii.	Power station II					
iii.	Power station III					
iv.	Power station IV					
	3. RES Generation					
(a)	Own generation					
i.	Power station I					
ii.	Power station II					
iii.	Power station III					
iv.	Power station IV					
(b)	CGS generation					
i.	Power station I					
ii.	Power station II					
iii.	Power station III					
iv.	Power station IV					
(c)	IPP`s generation					
i.	Power station I					
ii.	Power station II					
iii.	Power station III					
iv.	Power station IV					

FoR Technical Committee on Grid Integration of Renewable Energy (RE), with reference to regional cooperation and other options for managing intra-day load / generation variation due to RE or otherwise -- Record of Proceedings of the meeting held on 18.8.2017.

In order facilitate implementation of Framework on Renewables at State Level, FoR constituted a Technical Committee under the Chairmanship of Shri A.S. Bakshi, Member, CERC. The mandate given to the Committee *inter alia* includes evolving a roadmap for implementation of Framework on Forecasting, Scheduling and Deviation Settlement of Wind & Solar generating stations at State Level, implementation of ABT Framework, introduction of Ancillary Services and Reserves, implementation of Automatic Generation and Primary Control etc.

- 2. The Technical Committee in its meeting held on 28.3.2017 at Chennai, discussed the matter related to Co-operation among States for Optimum Utilization of their Generation Resources, amongst the other issues. During the discussion, it was decided that sub-groups be constituted in the Northern Region, Western Region and Southern Region (the three RE rich regions) headed by the Member Secretaries of the respective Regional Power Committees (RPCs). The Sub-groups were mandated to examine the feasibility and modality of co-operation among States in the respective region for ensuring optimum utilization of generation resources with least cost options for balancing across the region and submit their findings before the Technical Committee.
- 3. A meeting of the Heads / Representatives of the Sub-Groups was convened under the Chairmanship of Shri A.S.Bakshi, Member, CERC on 18.8.2017 in CERC, New Delhi to review the progress on framework for regional co-operation. The list of participants is at **Annexure I.**
- 4. The following emerged during the deliberations in the meeting:-
  - Of late, the States have recognized the value of electricity resource vis-à-vis the cost of generation. Some of the States are not willing to cooperate with other States in the Region on "cost" basis.
  - It was also observed that some of the Regions are predominantly "Surplus" in power, leaving little scope for co-operation within the region. This necessitates a national level framework / product for optimum resource utilization.
  - Various other options for handling intra-day load / generation variation due to RE or otherwise were also discussed as at **Annexure-II**, viz. (i) Banking; (ii) DAM price on PX as reference; (iii) Pool based on VC as approved by the Regulator and on payment of cost; (iv) Pool based on VC as approved by the Regulator and on payment of MC; (v) Pool based on auction for intra-day for the rest of the day; (vi) Pool based on auction for intra-day on hourly basis; (vii) Pool based on auction for intra-day on intra-hour basis i.e for 15 min. block-wise etc.
- 5. During the meeting it was decided to share with all RPCs the options raised therein and seek feedback.

#### Annexure - I

List of participants attended meeting of the Sub-Group under FOR Technical Committee Meeting held on 18.8.2017 under the Chairmanship of Shri A.S. Bakshi, Member, CERC

- 1. Shri A.S. Bakshi, Member, CERC
- 2. Dr. M.K. Iyer, Member, CERC
- 3. Shri M.A.K.P. Singh, Member Secretary, NRPC
- 4. Shri A. Balan, Member Secretary, WRPC
- 5. Shri S.R. Bhat, Member Secretary, SRPC
- 6. Shri S.C. Shrivastava, Chief (Engineering), CERC
- 7. Dr. S.K. Chatterjee, Joint Chief (Regulatory Affairs), CERC
- 8. Shri K.V.S. Baba, CEO, POSOCO
- 9. Shri S.K. Soonee, Advisor (POSOCO)
- 10. Smt. Shilpa Agarwal, Joint Chief (Engg.)
- 11. Shri S.S. Barpanda, GM, NLDC
- 12. Shri Samir Saxena, DGM, NLDC
- 13. Shri M.M. Chaudhari Deputy Chief (Engg.)
- 14. Smt. Shruti Deorah, Advisor (RE), CERC
- 15. Shri Anil, SRPC
- 16. Shri H.K. Pandey, S.E, NRPC
- 17. Shri Rajasekhar Devaguptapu, Regulatory Executive Officer, CERC
- 18. Shri Siddharth Arora, Research Officer, CERC

#### I. Options for Intra-Day / Hour Ahead transactions:

Seven options have been proposed for Hour Ahead Transactions.

#### Option-1: Banking

- Pros: Voluntary; No price transaction; Easy to implement
- Cons: Still bilateral; Opaque to cheaper options; True marginal cost of meeting demand not known; Elements of Cost and Value missing; No knowledge of gain or loss

#### Option-2: Day Ahead Market Price on Power Exchange as reference

- Pros: Well accepted reference price; Dispute free
- Cons: Very remote chance of availability of generation sources with marginal cost equal to or less than Day Ahead Market(DAM) price; Liquidity will always be an issue

# Option-3: Pool, based on variable cost as approved by the Regulator and on payment of cost

- Pros: Visibility of all options for purchase decision; Dispute free as regulator approved Variable Cost (VC); All resources get paid as per their cost or marginal cost; Improvement over option 2, liquidity
- Cons: Still based on cost and not on value; VC difficult to ascertain; Merchant plants cannot participate as their tariffs are not determined by regulator

# Option-4: Pool, based on variable cost as approved by the Regulator and on payment of marginal cost

- Pros: Same as Option 3; Improvement over Option 3 element of 'value' introduced because of marginal cost based payment
- Cons: VC difficult to ascertain; Merchant plants cannot participate as their tariffs are not determined by regulator; Payment based on marginal cost may lead to heart burn; still administered

#### Option-5: Pool, based on auction (intra-day for the rest of the day)

- Pros: Market Discovered Price; Dispute free; Not administered; Akin to DAM but closer to real time
- Cons: Preparedness of Power Exchange (PX); Discoms' decision making process; OA registry, a pre-requisite

#### Option-6: Pool, based on auction (hourly)

- Pros: Market Discovered Price; Dispute free; Not administered; Akin to DAM but closer to real time
- Cons: Preparedness of PX; Discoms decision making process; OA registry, a pre-requisite

#### Option-7: Pool, based on auction (intra-hour i.e. 15 min. block)

- Pros: Market Discovered Price; Dispute free; Not administered; Akin to DAM but closer to real time
- Cons: Preparedness of PX; Discoms' decision making process; OA registry, a pre-requisite

#### II. Illustration:

- a. Auction: 7.30 Hrs. 8.00 Hrs. window, transaction for <u>'rest of the day' (Intra-day : Option 5)</u> / <u>'for 9.00 10.00 Hrs.' (Hourly : Option 6)</u> / <u>'for 9.00 9.15 Hrs.' (Intra-hour : Option 7)</u>, and so on
- b. Generators can participate for sale of surplus power (over and above already scheduled on day-ahead basis)
- c. Sellers (other than generators) and buyers can participate for surplus / deficit vis-à-vis their schedule on day-ahead basis
- d. After the trade materializes under Option 5, 6 or 7 as the case may be, net schedule for the buyers and sellers shall be prepared, which will serve as reference point for DSM /
- e. However, payment for 'Day-ahead' transaction and 'Intra-day' (Option 5) / 'Hourly' (Option 6) / 'Intra-hour' (Option 7) transactions shall be settled separately based on the schedules for the respective segments
- f. Open Access Registry and delegation of decision making authority to operating level at Discom are pre-conditions to success of this framework.

\*\*\*

List of the ICT/AT	R/TRF belong	g to ISGS & IS	TS transm						
				Tap		Voltage (kV)	Present	Nominal	
	Voltage	Capacity	No of	provided in	No of	change per	Tap	Тар	
Name of S/S	level	(MVA)	ICT	which side	Taps	Tap	position	position	Make
Angul	765/400	1500	4	HV	23	4	12	12	NA
Gaya	765/400	1500	3	HV	23	4	12	12	NA
Jharsuguda	765/400	1500	2	HV	23	4	12	12	NA
New Ranchi	765/400	1500	2	HV	23	4	12	12	NA
New Sasaram	765/400	1500	2	HV	23	4	12	12	NA
Alipurduar	400/220	315	2	NA	NA	NA	NA	NA	NA
Baripada	400/220	315	2	HV	17	5	11	9	NA
Baripada	400/220	500	1	NA	NA	NA	NA	NA	NA
Biharshariff	400/220	315	3	HV	17	5	12	9	NA
Binaguri	400/220	315	2	HV	17	5	10	9	NA
Bolangir	400/220	315	2	HV	17	5	9B	9	NA
Chaibasa	400/220	315	2	HV	17	5	9B	9B	NA
Darbhanga	400/220	500	2	NA	NA	NA	NA	NA	NA
FSTPP	400/220	315	1	HV	17	5	11	9B	NA
Gaya	400/220	315	1	HV	17	5	12	9	NA
Gaya	400/220	500	1	HV	17	5	12	9	NA
Indravati	400/220	315	1	HV	17	5	9B	9	NA
Jamshedpur	400/220	315	3	HV	17	5	15	9	NA
Jeypore	400/220	315	2	HV	17	5	14	9	NA
Keonjhar	400/220	315	2	HV	17	5	9B	9B	NA
Kishangunj	400/220	500	2	HV	17	5	9B	9B	NA
Maithon	400/220	315	1	HV	17	5	9B	9B	NA
Maithon	400/220	500	1	HV	17	5	9B	9B	NA
Malda	400/220	315	2	HV	17	5	10	9	NA
Muzzaffarpur	400/220	315	2	HV	17	5	12	9B	NA
Muzzaffarpur	400/220	500	1	HV	17	5	12	9B	NA
New Purnea	400/220	500	2	HV	17	5	11	9	NA
Pandiabili	400/220	500	2	HV	17	5	9B	9B	NA
Parulia	400/220	315	2	HV	17	5	11	9	NA
Patna	400/220	315	1	HV	17	5	9B	9B	NA
Patna	400/220	500	1	HV	17	5	9B	9B	NA
Ranchi	400/220	315	2	HV	17	5	9B	9	NA
Rangpo	400/220	315	5	HV	17	5	9	9	NA
Rengali	400/220	315	2	HV	17	5	9	9	NA
Rourkela	400/220	315	2	HV	17	5	10	9	NA
Sasaram	400/220	315	1	HV	17	5	14	9	NA
Sasaram	400/220	500	1	HV	17	5	14	9	NA
Subhasgram	400/220	315	4	HV	17	5	9	9	NA
Subhasgram	400/220	500	1	HV	17	5	9	9	NA
TSTPP	400/220	315	2	HV	17	5	13	9	NA
Banka	400/132	200	2	HV	17	5	7	9	NA
Barh	400/132	200	2	NA	NA	NA E	NA 10	NA	NA
KhSTPP	400/132	200	2	HV	17	5	10	9	NA
Lakhisarai	400/132	200	2	HV	17	5	9	9	NA
Nabinagar	400/132	200	2	NA LV	NA 17	NA 1.4E	NA	NA 12	NA
Arrah	220/132 220/132	100	2	LV	17	1.65	9	13	NA
Arrah Baripada	220/132	160 160	1	LV	17 NA	1.65 NA	NA NA	13 NA	NA NA
			2	NA LV					NA NA
Birpara	220/132	160	2	LV	17 NA	1.65	12	13 NA	NA NA
Bolangir Dikchu	220/132 400/132	160 270	1 1	NA NA	NA NA	NA NA	NA NA	NA NA	NA NA
Malda	220/132	160	2	LV	17	1.65	10	13	NA NA
Malda	220/132	50	<u>Z</u> 1	LV	17	1.65	10	13	NA NA
Muzzaffarpur	220/132	100	1	NA NA	NA	NA	NA	NA	NA
NJP	220/132	100	2	LV	17	1.65	NA 9	13	NA NA
NJP NJP	220/132	160	<u>2</u> 1	LV	13	1.65	7	13	NA NA
Purnea	220/132	160	3	LV	17	1.65	9	13	NA
Rangpo	220/132	100	3	LV	17	1.65	NA	13	NA
Gangtok	132/66	50	2	HV	17	1.65	9B	9	NA
GariyiUK	132/00	υC		Пν	17	1.00	УD	У	INA

<sup>\*</sup> NA means data not available

List of the ICT/ATR/TRF belong to BSPHCL

LIST OF THE ICT/A	IV IVI DCIOII	I TO DOI THOL							
				Тар		Voltage (kV)	Present	Nominal	
	Voltage	Capacity	No of	provided in	No of	change per	Tap	Тар	
Name of S/S	level	(MVA)	ICT	which side	Taps	Тар	position	position	Make
Begusarai	220/132	100	2	HV	17	1.75	4	9	NA
Biharshariff	220/132	150	3	HV	17	2.75	4	5	NA
Bodhgaya	220/132	150	4	HV	25	1.85	9 (216.5 kV)	7	NA
Darbhanga	220/132	100	2	HV	13	2.75	10	9	NA
Dehri	220/132	100	4	HV	17	2.75	5	5	NA
Fatuah	220/132	100	4	HV	17	2.75	7	9	NA
Gopalgunj	220/132	100	2	HV	13	2.75	7	9	NA
Hazipur	220/132	100	3	HV	17	2.75	NA	9	NA
Khagul	220/132	100	3	HV	17	2.75	7	9	NA
Madhepura	220/132	100	2	NA	NA	NA	NA	NA	NA
Madhepura	220/132	160	1	NA	NA	NA	NA	NA	NA
MTPS	220/132	100	2	LV	17	1.65	1	9	NA
MUSHAHRI	220/132	160	2	HV	17	1.65	9	9	NA
Muzzaffarpur	220/132	100	3	HV	17	2.75	NA	9	NA
New Kishangunj	220/132	160	2	HV	17	2.75	NA	9	NA
Pusouli	220/132	150	2	HV	17	1.75	9	9	NA
Samastipur	220/132	160	2	LV	17	1.65	1	9	NA
Sipara	220/132	150	2	HV	17	1.65	9	9	NA
Sipara	220/132	160	1	HV	17	1.65	9	9	NA
Sonenagar	220/132	160	2	HV	17	2.75	NA	9	NA

<sup>\*</sup> NA means data not available

List of the ICT/ATR/TRF belong to JUVNL

LIST OF THE 10177T		,		•					
				Тар		Voltage (kV)	Present	Nominal	
	Voltage	Capacity	No of	provided in	No of	change per	Tap	Тар	
Name of S/S	level	(MVA)	ICT	which side	Taps	Тар	position	position	Make
Chaibasa	220/132	50	2	HV	17	2.75	5	9	
Chaibasa	220/132	150	2	HV	13	2.75	9	9	
Chandil	220/132	100	4	HV	17	2.75	9	5	
Dumka	220/132	150	2	HV	17	2.75	7	9	
Hatia	220/132	150	3	HV	17	2.75	5	9	
Lalmatia	220/132	100	2	HV	17	2.75	5	9	
Patratu	220/132	150	2	HV	17	2.75	12	9	
Ramchandrapur	220/132	150	2	HV	19	2.75	10	9	
Ramchandrapur	220/132	150	1	HV	17	2.75	5	9	

<sup>\*</sup> NA means data not available

List of the ICT/ATR/TRF belong to DVC

				Тар		Voltage (kV)	Present	Nominal	
	Voltage	Capacity	No of	provided in	No of	change per	Тар	Tap	
Name of C/C			ICT	•			•	•	Maka
Name of S/S	level	(MVA)		which side	Taps	Тар	position	position	Make
Bokaro A	400/220	315	2	NA	NA	NA	NA	NA	NA
Koderma	400/220	315	2	HV	17	5	9B	9B	NA
RTPS	400/220	315	2	NA	NA	NA	NA	NA	NA
TISCO	400/220	315	2	HV	17	5	9B	9B	NA
Bokaro B	220/132	150	2	HV	17	2.75	NA	9	NA
Borojora	220/132	150	2	HV	17	2.75	7	9	NA
CTPS	220/132	150	2	HV	17	2.75	NA	9	NA
CTPS	220/132	100	2	LV	17	1.65	NA	9	NA
Giridih	220/132	150	1	HV	17	2.75	9B	9B	NA
Giridih	220/132	160	1	HV	17	2.75	9B	9B	NA
Jamshedpur	220/132	150	1	HV	17	2.75	3	9	NA
Jamshedpur	220/132	160	1	HV	17	2.75	3	9	NA
Kalyaneswari	220/132	150	3	HV	17	2.75	11	9	NA
Ramgarh	220/132	150	2	HV	17	2.75	10	9	NA
Waria	220/132	150	2	HV	17	2.75	NA	9	NA
Borojora	220/33	50	2	NA	NA	NA	NA	NA	NA
Burnpur	220/33	50	2	NA	NA	NA	NA	NA	NA
Durgapur	220/33	80	1	NA	NA	NA	NA	NA	NA
Giridih	220/33	80	1	NA	NA	NA	NA	NA	NA
Muchipara	220/33	80	1	NA	NA	NA	NA	NA	NA
Muchipara	220/33	50	2	NA	NA	NA	NA	NA	NA

<sup>\*</sup> NA means data not available

List of the ICT/ATR/TRF belong to GRIDCO

List of the IC1/A	IR/ IRF belong	g to GRIDCO							
				Tap		Voltage (kV)	Present	Nominal	
	Voltage	Capacity	No of	provided in	No of	change per	Tap	Тар	
Name of S/S	level	(MVA)	ICT	which side	Taps	Тар	position	position	Make
Indravati	400/220	315	1	HV	17	5	9B	9B	NA
Mendasal	400/220	315	2	HV	17	5	9	9	NA
Meramundali	400/220	315	2	HV	17	5	10	9	NA
New Duburi	400/220	315	2	HV	17	5	9	9	NA
STERLITE	400/220	315	2	HV	17	5	11	9	NA
Atri	220/132	160	1	NA	NA	NA	NA	NA	NA
Balasore	220/132	160	2	LV	17	1.65	NA	9	NA
Bhanjanagar	220/132	160	2	LV	17	1.65	NA	9	NA
Bidansi	220/132	160	1	LV	17	1.65	NA	9	NA
Bidansi	220/132	100	2	LV	17	1.65	NA	9	NA
Budipadar	220/132	160	2	LV	17	1.65	NA	9	NA
Chandaka	220/132	100	3	LV	17	1.65	NA	9	NA
Duburi	220/132	100	3	LV	17	1.65	NA	9	NA
Jaynagar	220/132	100	2	HV	17	2.75	NA	9	NA
Joda	220/132	100	3	LV	33	-0.83	11	17	NA
Katapalli	220/132	160	1	LV	17	1.65	NA	9	NA
Katapalli	220/132	100	2	LV	17	1.65	NA	9	NA
Mendasal	220/132	160	2	NA	NA	NA	NA	NA	NA
Meramundali	220/132	100	3	LV	17	1.65	NA	9	NA
Narendrapur	220/132	160	2	NA	NA	NA	NA	NA	NA
Narendrapur	220/132	100	1	LV	17	1.65	NA	13	NA
Paradeep	220/132	160	1	NA	NA	NA	NA	NA	NA
Paradeep	220/132	100	1	NA	NA	NA	NA	NA	NA
Puri	220/132	160	2	NA	NA	NA	NA	NA	NA
New Bolangir	220/132	160	2	LV	17	1.65	NA	9	NA
Samungara	220/132	NA	NA	HV	17	2.75	NA	9	NA
Tarkera	220/132	100	4	LV	17	1.65	NA	9	NA
Theruvali	220/132	100	2	LV	17	1.65	NA	9	NA
TTPS	220/132	160	2	LV	17	1.65	NA	9	NA
TTPS	220/132	150	1	LV	33	-0.83	NA	17	NA

<sup>\*</sup> NA means data not available

List of the ICT/ATR/TRF belong to WBPDCL/WBSETCL/WBSEDCL

List of the IC1/A1	K/ IKF Deloli	J TO WEPDEL	./ VVD3ETCL	Тар		Voltage (kV)	Present	Nominal	
	Voltage	Capacity	No of	provided in	No of	change per	Tap	Тар	
N. 50/0	ū						•		
Name of S/S	level	(MVA)	ICT	which side	Taps	Тар	position	position	Make
Arambag	400/220	315	4	HV	17	5	13	9	NA
Bakreswar	400/220	315	2	HV	17	5	11	9	NA
Bidhannagar	400/220	315	2	HV	17	5	9B	9	NA
Gokarna	400/220	315	2	NA	NA	NA	NA	NA	NA
Jeerat	400/220	315	4	LV	17	2.88	11	NA	NA
Kharagpur	400/220	315	3	HV	17	5	7	9	NA
KTPP	400/220	315	2	HV	17	5	12	9	NA
Sagardighi	400/220	315	11	HV	17	5	NA	9	NA
Arambag	220/132	160	1	LV	17	1.65	NA	9	NA
Arambag	220/132	100	1	LV	17	1.65	NA	9	NA
Asansol	220/132	160	2	LV	17	1.65	NA	9	NA
BBGS	220/132	NA	2	HV	16	5.55	10	9	NA
Bantala	220/132	160	1	NA	NA	NA	NA	NA	NA
Bidhannagar	220/132	160	2	LV	17	1.65	NA	9	NA
Dalkhola	220/132	160	2	LV	17	1.65	NA	9	NA
Dharma	220/132	160	2	LV	17	1.65	NA	9	NA
Domjur	220/132	160	2	LV	17	1.65	NA	9	NA
DPL (AREVA)	220/132	160	1	LV	17	1.65	9	9	NA
DPL (BHEL)	220/132	100	1	LV	17	1.65	9	9	NA
DPL (China)	220/132	160	1	HV	19	2.75	10	10	NA
EMSS	220/132	160	3	NA	NA	NA	NA	NA	NA
Egra	220/132	160	2	NA	NA	NA	NA	NA	NA
Foundry Park	220/132	160	2	NA	NA	NA	NA	NA	NA
Gokarna	220/132	160	2	LV	17	1.65	NA	9	NA
Howrah	220/132	150	3	LV	17	1.65	NA	9	NA
Howrah	220/132	160	1	NA	NA	NA	NA	NA	NA
Jeerat	220/132	160	3	LV	17	1.65	NA	9	NA
Kasba	220/132	160	2	LV	17	1.65	NA	9	NA
Kasba	220/132	150	2	NA	NA	NA	NA	NA	NA
Kharagpur	220/132	160	2	NA	NA	NA	NA	NA	NA
Krishnanagar	220/132	160	2	LV	17	1.65	NA	9	NA
KTPP	220/132	160	1	LV	17	1.65	NA	9	NA
KTPP	220/132	150	2	LV	17	1.65	NA	9	NA
Laxmikantapur	220/132	160	3	LV	17	1.65	NA	9	NA
New Bishnupur	220/132	160	3	NA	NA	NA	NA	NA	NA
New Haldia	220/132	160	2	NA	NA	NA	NA	NA	NA
N Jalpaiguri	220/132	160	2	LV	17	1.65	NA	9	NA
Rajarhat	220/132	160	2	NA	NA	NA	NA	NA	NA
Rishra	220/132	160	2	LV	17	1.65	NA	9	NA
Santaldih	220/132	100	1	LV	17	1.65	NA	9	NA
Santaldih	220/132	130	1	NA	NA	NA	NA	NA	NA
Satgachia	220/132	160	2	LV	17	1.65	NA	9	NA
Subhasgram	220/132	160	2	NA	NA	NA	NA	NA	NA
Vidyasagar Park	220/132	160	2	NA	NA	NA	NA	NA	NA

<sup>\*</sup> NA means data not available

List of the GT situated in the	Eastern Regio	n								
				Тар		Voltage (kV)	Present	Nominal		
	Voltage	Capacity		provided in	No of	change per	Tap	Tap		
Name of Generating Unit	level	(MVA)	No of GT	which side	Taps	Tap	position	position	Owner	Make
APNRL I	400/16.5	330	1	HV	19	4.83	8(420 KV)	NA	APNRL	NA
APNRL II	400/16.5	340	1	HV	5	10.5	3 (420 KV)	NA	APNRL	NA
CHPC - I	220/11	105.882353	1	HV	5	4.5	NA	4 (220 KV)	Bhutan	NA
Nabinagar (250 MW)	NA	NA	1	NA	NA	NA	NA	NA	BRBCL	NA
Nabinagar (250 MW)	NA 120/11	NA 147 OF OOO 4	1	NA	NA	NA 2.475	NA O (140 F K) ()	NA 2 (120 KM)	BRBCL	NA
BTPS VI & VII MTPS - I & II	139/11 230/11	147.058824 164.705882	2	HV HV	5 6	3.475 5.75	2 (142.5 KV) NA	3 (139 KV) 4 (230 KV)	BSPHCL BSPHCL	NA NA
MTPS -III (195 MW)	NA NA	NA	1	NA NA	NA	NA	NA NA	4 (230 KV) NA	BSPHCL	NA
BBGS I & II	132/16.5	294.117647	2	LV	9	0.4125	6 (16.09 KV)		CESC	NA
BBGS III	235/16.5	294.117647	1	HV	9	5.875	5 (235 KV)	5 (235 KV)	CESC	NA
Jorethang (48 MW)	NA	NA	2	NA	NA	NA	NA	NA	DEPL	NA
Bokaro A (500 MW)	NA	NA	1	NA	NA	NA	NA	NA	DVC	NA
Bokaro B (210 MW)	NA	NA	3	NA	NA	NA	NA	NA	DVC	NA
CTPS (140 MW)	132/13.8	164.705882	2	HV	5	3.3	NA	3 (132 KV)	DVC	NA
CTPS B (210 MW)	NA	NA	2	NA	NA	NA	NA	NA	DVC	NA
DSTPS I & II	400/21	588.235294	2	HV	9	10.5	5 (420 KV)	7 (399 KV)	DVC	NA
Koderma I & II	400/21	588.235294	2	HV	9	10.5	5 (420 KV)	7 (399 KV)	DVC	NA
Mejia I - IV	220/15.75	247.058824	4	HV	5	5.5	NA	3 (220 KV)	DVC	NA
Mejia V & VI Mejia VII & VIII	220/16.5 400/21	294.117647 588.235294	2	HV HV	5 9	6 10.5	NA 4 (430.5)	NA 7 (399 KV)	DVC DVC	NA NA
RTPS (600 MW)	400/21 NA	NA	2	NA NA	NA NA	NA	4 (430.5) NA	7 (399 KV) NA	DVC	NA
Waria IV	220/16	294.117647	1	HV	5	5.5	NA	3 (220 KV)	DVC	NA
Chujachen (110 MW)	NA NA	NA	2	NA NA	NA	NA NA	NA	NA NA	GIPL	NA
GMR (350 MW)	NA	NA	3	NA	NA	NA	NA	NA	GKEL	NA
Haldia (300 MW)	NA	NA	2	NA	NA	NA	NA	NA	HEL	NA
Ind Bharat (350 MW)	NA	NA	1	NA	NA	NA	NA	NA	IBEUL	NA
Ind Bharat (350 MW)	NA	NA	1	NA	NA	NA	NA	NA	IBEUL	NA
IBTPS I & II	220/15.75	294.117647	2	HV	5	5.5	NA	3 (220 KV)	IBTPS	NA
JITPL (600 MW)	NA	NA	2	NA	NA	NA	NA	NA	JITPL	NA
SUBARNAREKHA	132/11	94.1176471	2	HV	5	3.3	2 (138.6 KV)	4 (132 KV)	JUVNL	NA
Maithon RB (525 MW)	NA	NA	2	NA	NA	NA	NA	NA	MPL	NA
NALCO I - VIII	220/10.5	141.176471	8	HV	5	5.875	NA 2 (400 L) ()	NA 2 (400 LV)	NALCO	NA
Teesta V (170 MW) Barh IV & V (660 MW)	400/13.8 NA	70 NA	9	HV NA	5 NA	10 NA	3 (400 kV) NA	3 (400 kV) NA	NHPC NTPC	ALSTOM NA
FSTPP -I	400/15.75	247.058824	1	HV	5	10.5	3 (420 KV)	5 (399 KV)	NTPC	NA
FSTPP -II & III	400/15.75	247.058824	2	HV	13	5.25	6 (414.8 KV)	9(399 KV)	NTPC	NA
FSTPP -IV, V & VI	400/21	588.235294	3	HV	13	5.25	7 (409.5 KV)	9(399 KV)	NTPC	NA
KhSTPP I, II, III & IV (210 MW)	NA	NA	4	NA	NA	NA	NA	NA	NTPC	NA
KhSTPP V, VI & VII (500 MW)	NA	NA	3	NA	NA	NA	NA	NA	NTPC	NA
TSTPP I & II	400/21	588	2	HV	13	5.25	8 (404.3 KV)	9(399 KV)	NTPC	NA
Balimela I - VI	132/11	70.5882353	6	HV	5	3.615	NA	NA	OHPC	NA
Balimela VII - VIII	132/11	88.2352941	2	HV	7	3.615	NA	NA	OHPC	NA
Rengali I - V	220/11	58.8235294	5	HV	5	5	NA	NA	OHPC	NA
U Indravati (150 MW)	NA 220/11	NA	4	NA	NA	NA ( 25	NA	NA	OHPC	NA
U Kolab I - IV TTPS I - IV	220/11 132/13.8	94.1176471 70.5882353	4	HV	6	6.25 3.2	NA	NA	OHPC OPGC	NA NA
TTPS V - VI	132/13.6	129.411765	2	HV HV	6	6	NA NA	NA NA	OPGC	NA
SEL	242.4/22	750	4	HV	5	5.45	3 (242.45)	3 (242.45)	SEL	NA
Dikchu (48 MW)	NA	NA	2	NA	NA	NA NA	NA	NA	SKPPPL	NA
Teesta III (200 MW)	NA	NA	6	NA	NA	NA	NA	NA	TUL	NA
TENUGHAT	220/15.75	294.117647	2	HV	9	5.5	1 (231 KV)	3 (220 KV)	TVNL	NA
BKTPS	420/15.75	247.058824	5	HV	5	10.5	3 (420 KV)	NA	WBPDCL	NA
BTPS I, II & IV	132/13.2	117.647059	3	HV	7	3.3	2 (135.3 KV)	3 (132 KV)	WBPDCL	NA
BTPS V	138/15.75	276.470588	1	HV	3	3.45	3 (134.55)	2 (138 KV)	WBPDCL	NA
DPL III & V	132/10.5	100	2	HV	18	1.88	8 (135.76)	10 (132 KV)	WBPDCL	NA
DPL VI	235/11	125	1	HV	5	5.87	3(235 KV)	3(235 KV)	WBPDCL	NA
DPL VIII	220/20	370	1	HV	5	5.87	3(235 KV)	NA	WBPDCL	NA
DPL VIII	220/16.5	315	1	HV	5	5.87	3(235 KV)	NA NA	WBPDCL	NA NA
KTPS I, II, III KTPS IV, VI	220/15.75 420/15.75	247.058824 247.058824	3 2	HV HV	5 5	5.75 10.5	3 (230 KV) 4 (409.5 KV)	NA 3 (420 KV)	WBPDCL WBPDCL	NA NA
KTPS V	420/15.75	247.058824	1	HV	5	10.5	5 (399 KV)	3 (420 KV)	WBPDCL	NA NA
Sagardighi I & II	400/20	352.941176	2	HV	5	10.3	NA NA	3 (420 KV)	WBPDCL	NA
STPS	220/13.8	164.705882	4	HV	5	5.5	NA	3 (220 KV)	WBPDCL	NA
STPS V & VI	220/16.5	294.117647	2	HV	5	5.875	4 (229.13)	NA	WBPDCL	NA
		•	-		•					

<sup>\*</sup> NA means data not available

## **Checklist for Submission of new transmission elements for updation in Protection Database**

NAME OF ORGANISATION: FOR THE MONTH OF:

**SUBSTATION DETAIL:** 

SI No	DETAILS OF ELEMENTS	DATA TYPE	Status of Submission (Y/N)	Remarks
1	TRANSMISSION LINE	LINE LENGTH, CONDUCTOR TYPE, VOLTAGE GRADE		
2	POWER TRANSFORMER	NAMEPLATE DETAILS		
3	GENERATOR	TECHNICAL PARAMETERS		
4	CURRENT TRANSFORMER	NAMEPLATE DETAILS		
5	VOLTAGE TRANSFORMER	NAMEPLATE DETAILS		
6	RELAY DATA	MAKE, MODEL and FEEDER NAME		
7	RELAY SETTINGS	NUMERICAL RELAYS: CSV or XML file extracted from Relay ELECTROMECHANICAL RELAYS: SNAPSHOT of RELAY		
8	REACTOR	NAMEPLATE DETAILS		
9	CAPACITOR	NAMEPLATE DETAILS		
9	UPDATED SLD			

**SIGNATURE:** 

NAME OF REPRESENTATIVE:

**DESIGNATION:** 

CONTACT:

E-MAIL ID:

S.No	Regio n	State	Sub-Station	Owner/ Utility	S/S type		L PANE L QTY	y status		n	laying	CT/PT/DI terminatio n	sioning	Integration		Remarks
			78			296	175	74	75	66	65	61	62	42	58	
1	ER-II	West Bengal		WBSETCL	CR	3	1	Yes	Yes	done	done	done	done	done	done	
2	ER-II		BAKRESHWAR TPS	WBSETCL	CR	4	1	Yes	Yes	done	done	done	done	done	done	
3	ER-II	West Bengal		WBSETCL	CR	3	1	Yes	Yes	done	done	done	done	done	done	CAT line lidell toite CAT
4	ER-II	,	JEERAT	WBSETCL	CR	2	7	Yes	Yes	done	done	done	done	done	pending	SAT pending as customer didn't agree to witness SAT.
57	ER-II	West Bengal	Alipurduar	Powergrid	CR	6	7	Yes	Yes	partially done	partially done	partially done	done	Pending	pending	Work started on 22.12.2016. 4 PMU panels and network panel installed. Rest 2 PMU panels could not be erected because location not finalised. Cable laying and termination at PMU panel completed for 6 feeders. CT/PT interfacing pending due to unavailability of shutdown. PGCIL is asking to take DI points from field, which is not in scope. Work is held up. Team demobilised.
6	ER-II	West Bengal	KASBA	WBSETCL	CR	3	1	Yes	Yes	done	done	done	done	done	done	
7	ER-II	DVC	DSTPS	DVC	CR	2	1	Yes	Yes	done	done	done	done	Pending	done	Communication Link not available.
67	ER-I	BIHAR	BANKA	Powergrid	Kiosk	4	5	Yes	Yes	done	done	done	done	Pending	pending	Integration is in progress, SAT pending.
9	ER-II	DVC	MEJIA-B	DVC	CR	2	1	Yes	Yes	done	done	done	done	done	done	Integrated on 07.12.2016
45	ER-II	Jharkhand	Bokaro TPS	DVC	CR	1	1	Yes	Yes	done	done	done	done	Pending	done	S/S couldn't be integrated because distance between PMU panel and SDH is more than 100 mtrs.
11	ER-II	DVC	Raghunathpur TPS	DVC	CR	3	1	Yes	Yes	done	done	done	done	done	done	
33	Odisha	Orissa	Bolangir	Powergrid	CR+Kiosk	2	3	Yes	Yes	done	done	done	done	Pending	done	Communication Link not available.
13	ER-II	DVC	Bokaro	DVC	CR	2	1	Yes	Yes	done	done	done	done	done	done	PMU integrated on 24.06.2016
14	ER-II	DVC	CTPS(Chanderpura)	DVC	CR	2	1	Yes	Yes	done	done	done	done	Pending	done	S/S couldn't be integrated because distance between PMU panel and SDH is more than 100 mtrs.
78	ER-I	Bihar	Barauni PP	Bihar	CR	0	0	No	No	N/A	N/A	N/A	N/A	N/A	N/A	Substation will be deleted, verbal communication from PG.
16	Odisha	Orissa	MENDHASAL	OPTCL	CR	2	1	Yes	Yes	done	done	done	done	done	done	
17	Odisha	Orissa	MERAMANDALI	OPTCL	CR	6	2	Yes	Yes	done	done	done	done	done	done	
18	Odisha	Orissa	RENGALI	OPTCL	CR	2	1	Yes	Yes	done	done	done	done	done	done	Integrated on 22.06.2017
37	Odisha	Orissa	GMR	GMR	Kiosk	3	4	Yes	Yes	done	done	done	done	Pending	pending	SDH Panel not commisioned, powergrid supervision required for SAT activity
20	Odisha	Orissa	BALIMELA(H)	OPTCL	CR	3	1	Yes	Yes	done	done	done	done	done	done	
21	ER-II	West Bengal	Durgapur	Powergrid	CR	5		Yes	Yes	done	done	done	done	done	done	PMU integrated on 30.05.2016.
15	Odisha	Orissa	Budhipadar	OPTCL	CR	10	0	No	Yes	N/A	N/A	N/A	N/A	N/A	N/A	Under Manufacturing. Will be dispatched in next month.
23	Odisha	Orissa	Indrawati	Powergrid	CR	2	1	Yes	Yes	done	done	done	done	Pending	done	Communication Link not available.
24	Odisha	Orissa	Indrawati HPS	OPTCL	CR	1	1	Yes	Yes	done	done	done	done	done	done	Team deployed in substation. Permission for panel installation & cable laying given but no work permission in existing control panel is given. Team was idle for more than. 10 days.
25	Odisha		JEYPORE	Powergrid		2		Yes		done	done	done	done	Pending	done	Communication Link not available.
26	ER-II	West Bengal		Powergrid		7		Yes		done	done	done	done	done	done	PMU integrated on 21.06.2016.
27	ER-II	West Bengal		Powergrid		2		Yes	Yes	done	done	done	done	done	done	PMU integrated on 24.06.2016
28	Odisha		Rengali	Powergrid		2		Yes	Yes	done	done	done	done	done	done	PMU integrated on 04.05.2016
29	Odisha		ROURKELA	Powergrid		5		Yes	Yes	done	done	done	done	done	done	PMU integrated on 21.04.2016 PMU integrated on 28.07.2016
30	ER-II	West Bengal	IBINAGUN	Powergrid	CR	7	2	Yes	Yes	done	done	done	done	done	done	Pivio integrated on 28.07.2016

#### PMU Installation and commissioning status of ER as on 22.07.2017

S.No	Regio n	State	Sub-Station	Owner/ Utility	S/S type	PMU	TOTA L PANE L QTY		Cable Delivery status	Erectio n	Cable laying	CT/PT/DI terminatio n	Commis sioning	Integration	SAT	Remarks
31	ER-II	West Bengal	SUBHASHGRAM	Powergrid	Kiosk	2	1	Yes	Yes	done	done	done	done	done	done	PMU integrated on 22.06.2016
32	Odisha	Orissa	Baripada	Powergrid	CR	3	1	Yes	Yes	done	done	done	done	done	done	PMU integrated on 30.01.2017.
75	ER-I	Jharkhand	Jharkhand Pool (Chand	Powergrid	Kiosk	4	1	Yes	Yes	done	done	done	done	Pending	done	S/S couldn't be integrated because distance between PMU panel and SDH is more than 100 mts.
34	Odisha	Orissa	ANGUL	Powergrid	Kiosk	10	11	Yes	Yes	done	done	done	done	done	done	PMU integrated on 24.03.2017.
35	Odisha	Orissa	Keonjhar	Powergrid	CR	2	3	Yes	Yes	done	done	done	done	done	done	PMU integrated on 18.01.2017.
36	Odisha	Orissa	Jharsuguda	Powergrid	Kiosk	8	9	Yes	Yes	done	done	done	done	done	done	PMU integrated on 29.07.2016
74	ER-I	Bihar	Kishanganj (karandegh	Powergrid	CR	4	1	Yes	Yes	done	done	done	done	Pending	done	S/S couldn't be integrated because distance between PMU panel and SDH is more than 100 mts.
8	ER-II	DVC	Kodarma TPS	DVC	CR	3	1	Yes	Yes	done	done	done	done	Pending	done	SDH panel does not exist.
39	ER-II	West Bengal	Baharampur	Powergrid	CR	2	3	Yes	Yes	done	done	done	done	done	done	PMU integrated on 10.05.2016
40	ER-II	West Bengal	Birpara	Powergrid	CR	4	1	Yes	Yes	done	done	done	done	done	done	PMU integrated on 15.07.2016.
41	ER-II	DVC	CTPS B	DVC	CR	3	1	Yes	Yes	done	done	done	done	done	done	CT cable laying permission. I&C done. mom/sat signature pending from powergrid end.
42	ER-II	DVC	KALYANESWARI	DVC	CR	4	1	Yes	Yes	done	done	done	done	done	done	PMU integrated on 02.01.2017.
43	ER-II	DVC	PARULIA	DVC	CR	5	2	Yes	Yes	done	done	done	done	done	done	PMU integrated on 21.02.2017.
44	ER-II	West Bengal	Purulia PSP	WBSETCL	CR	2	1	Yes	Yes	done	done	done	done	done	done	
66	ER-I	BIHAR	LakhiSarai	Powergrid	Kiosk	4	5	Yes	Yes	done	done	done	done	Pending	done	SAT completed. Integration planed
46	ER-II	West Bengal	Durgapur TPS	DVC	CR	3	1	Yes	Yes	done	done	done	done	done	done	
73	ER-I	Jharkhand	Daltonganj	Powergrid	Kiosk	2	3	Yes	Yes	N/A	N/A	N/A	N/A	N/A	N/A	Site on-hold as Substation is under construction.
22	ER-II	West Bengal	FARRAKA	NTPC	CR	5	2	Yes	Yes	done	done	pending	pending	pending	pending	Termination pending due to no permission for shutdwon
54	Odisha	Orissa	Ind barath	Ind barath	Kiosk	1	1	Yes	Yes	pending	pending	pending	pending	pending	pending	Permission awaited
10	ER-II	DVC	Maithon RB TPS	DVC	CR	2	1		Yes	done	done	done	done	Pending	done	Work started on 04.07.2016. Panel shifted. Team demobilised due to access issue and panel location issue. Team deputed again 18th August, I&C done, integration pending due to communication break with control center.
51	Odisha	Orissa	Jindal	JITPL	CR	2	1		Yes	pending	pending	pending	pending	pending	pending	Permission awaited
5	ER-II	West Bengal	Kolaghat TPS	WBSETCL	CR	4	1		Yes	done	done	pending	pending	Pending	pending	Work under progress
52 55	Odisha ER-II	Orissa Sikkim	Monnet New Melli	Monnet Powergrid	CR CR	0	0		Yes N/A	pending N/A	pending N/A	pending N/A	pending N/A	pending N/A	pending N/A	Permission awaited BOQ submitted, yet to be approved. Substation will be deleted, verbal communication from PG.
76	ER-I	Jharkhand	Patratu	Jharkhand	CR	3	1	Yes	Yes	N/A	N/A	N/A	N/A	N/A	N/A	
53	Odisha	Orissa	Strelite	Strelite	CR	3	1		Yes	done	done	done	done	pending	done	SDH not commisioned
48	Odisha	Orissa	TALCHER	NTPC	CR	5	2		Yes	pending	pending	pending	pending	pending	pending	Permission awaited
58	ER-II	West Bengal	Rajarhat	Powergrid	CR	2	1		Yes	done	pending	pending	pending	Pending	pending	Site on-hold. Work withheld due to localite agitation issue.
59	ER-I	Jharkhand	JAMSHEDPUR	Powergrid	CR	6	2	Yes	Yes	done	done	done	done	done	done	PMU integrated on 14.02.2017
60	ER-I	BIHAR	Kahalgaon(KHSTPP)	NTPC	CR	6	2	Yes	Yes	done	done	pending	pending	Pending	pending	Work on-hold. NTPC asked to use Armoured cable. Out of scope. Team idemobilized from site. Site assumed as closed as per PRM in Kolkatta.
61	ER-I	BIHAR	Purnea	Powergrid	CR	6	2	Yes	Yes	done	done	done	done	done	done	PMU integrated on 13.04.2017

#### PMU Installation and commissioning status of ER as on 22.07.2017

S.No	Regio n	State	Sub-Station	Owner/ Utility	S/S type	PMU	L		Cable Delivery status	Erectio n	Cable laying	CT/PT/DI terminatio n	Commis sioning	Integration	SAT	Remarks
62	ER-I	BIHAR	PATNA	Powergrid	Kiosk	6	7	Yes	Yes	done	done	done	done	done	done	PMU integrated on 11.04.2017
63	ER-I	Jharkhand	RANCHI	Powergrid	Kiosk	12	13	Yes	Yes	done	done	done	done	done	done	
64	ER-I	BIHAR	SASARAM(Pusauli)	Powergrid	CR+Kiosk	9	3	Yes	Yes	done	done	done	done	done	done	
65	ER-I	BIHAR	BARH	NTPC	CR	4	1	Yes	Yes	done	done	done	done	Pending	done	Communication Link not available.
12	ER-II	DVC	MEJIA	DVC	CR	5	2	Yes	Yes	done	done	done	done	Pending	done	S/S couldn't be integrated because distance between PMU panel and SDH is more than 100 mtrs.
38	ER-II	Sikkim	RANGPO	Powergrid	CR	4	1	Yes	Yes	done	done	done	done	Pending	done	S/S couldn't be integrated because distance between PMU panel and SDH is more than 100 mtrs.
68	ER-I	Jharkhand	Chaibasa	Powergrid	Kiosk	4	5	Yes	Yes	done	done	done	done	done	done	
69	ER-I	BIHAR	765kv Gaya	Powergrid	Kiosk	11	12	Yes	Yes	done	done	done	done	done	done	PMU integrated on 24.02.2017
70	ER-I	Jharkhand	765/400kV Ranchi (N)	Powergrid	Kiosk	8	9	Yes	Yes	done	done	done	done	done	done	PMU integrated on 24.02.2017
71	ER-I	Bihar	Biharshariff	Powergrid	CR	9	3	Yes	Yes	done	done	done	done	done	done	
72	ER-I	Bihar	MUZAFFAPUR	Powergrid	CR	5	2	Yes	Yes	done	done	done	done	done	done	
49	ER-II	Sikkim	TEESTA	NHPC	CR	1	1	Yes	Yes	done	done	pending	done	done	pending	SAT due to no supervision & & interfacing pending which is to be done by NHPC/PG whenever shutdwon will be available as per PRM
77	ER-I	Jharkhand	Tenughat	Jharkhand	CR	2	1	Yes	Yes	done	done	done	done	Pending	done	SDH panel not commisioned
19	Odisha	Orissa	U.KOLAB	OPTCL	CR	2	1			done	done	done	done	Pending	done	Communication Link not available.
56	ER-II	Sikkim	TT Pool	Powergrid	CR	0	0	No	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Substation deleted, verbal communication from PG.
50	Odisha	Orissa	Uttara	Powergrid	CR	2	1	Yes	Yes	done	done	done	done	Pending	done	Communication link from s/s to ERLDC and NTAMC to be provided by PGCIL.
47	Odisha	Orissa	TTPS(Talcher)	OPTCL	CR	3	1	Yes	Yes	pending	pending	pending	pending	pending	pending	Permission awaited

#### **ER PMU site activity Summary:**

SI. No.	Region	Utility	As per approve	ed BOQ	Sup	plied	Ins	talled	Commi	issioned	Integrated to ERLDC/ SLDC	
			No. of Substations	No. of PMU	S/S	PMU	S/S	PMU	S/S	PMU	S/S	PMU
1	ER-I	Powergrid	15	94	15	94	14	92	14	92	10	76
2	ER-I	NTPC	2	10	2	10	2	10	1	4	0	0
3	ER-I	Jharkhand	2	5	2	5	1	2	1	2	0	0
4	ER-I	Bihar	1	0	0	0	0	0	0	0	0	0
	ER-I	Total	20	109	19	109	17	104	16	98	10	76
1	ER-II	Powergrid	12	41	11	42	9	35	8	33	7	29
	ER-II	NHPC	1	1	1	1	1	1	1	1	1	1
2	ER-II	NTPC	1	5	1	5	1	5	0	0	0	0
3	ER-II	DVC	13	37	13	37	13	37	13	37	7	22
4	ER-II	WBSETCL	7	21	7	21	7	21	6	17	6	17
	ER-II	Total	34	105	33	106	31	99	28	88	21	69
1	Odisha	Powergrid	10	38	10	38	10	38	10	38	6	30
2	Odisha	OPTCL	8	29	7	19	6	16	6	16	5	14
3	Odisha	NTPC	1	5	1	5	0	0	0	0	0	0
4	Odisha	IPP	5	10	5	10	2	6	2	6	0	0
	Odisha	Total	24	82	23	72	18	60	18	60	11	44
						•		•		•		
	ER	Total	78	296	75	287	66	263	62	246 Page 3	of 2 42	189

## Anticipated Power Supply Position for the month of Feb-18

	SL.NO	PARTICULARS	PEAK DEMAND MW	ENERGY MU
1	I	BIHAR	141.66	NIO
	i)	NET MAX DEMAND	3900	2000
	ii)	NET POWER AVAILABILITY- Own Source (including bilateral)	341	148
	l	- Central Sector	2724	1395
	iii)	SURPLUS(+)/DEFICIT(-)	-835	-457
	,	Som Ess(i) BEHOIT()	555	431
2		JHARKHAND		
	i)	NET MAX DEMAND	1250	750
	ii)	NET POWER AVAILABILITY- Own Source (including bilateral)	390	242
		- Central Sector	551	268
	iii)	SURPLUS(+)/DEFICIT(-)	-309	-239
3		DVC		
	i)	NET MAX DEMAND (OWN)	2770	1553
	ii)	NET POWER AVAILABILITY- Own Source	4892	2409
		- Central Sector	489	281
		Long term Bi-lateral (Export)	1300	874
	iii)	SURPLUS(+)/DEFICIT(-)	1310	263
4		ORISSA		
,	i)	NET MAX DEMAND	4000	2184
	ii)	NET POWER AVAILABILITY- Own Source	3022	1616
	l "'	- Central Sector	1110	606
	iii)	SURPLUS(+)/DEFICIT(-)	132	38
	,		.52	
5		WEST BENGAL		
5.1		WBSEDCL		
	i)	NET MAX DEMAND (OWN)	5820	2827
	ii)	CESC's DRAWAL	0	0
	iii)	TOTAL WBSEDCL'S DEMAND	5820	2827
	iv)	NET POWER AVAILABILITY- Own Source	3779	1877
	Ī	- Import from DPL	181	0
	Ī	- Central Sector	2357	1001
	v)	SURPLUS(+)/DEFICIT(-)	497	51
	vi)	EXPORT (TO B'DESH & SIKKIM)	5	3
		nni.		
5.2		DPL NET MAY DEMAND	245	170
	i)	NET MAX DEMAND	245	170
	ii)	NET POWER AVAILABILITY	426	170
	iii)	SURPLUS(+)/DEFICIT(-)	181	0
5.3		CESC		
5.5	i)	NET MAX DEMAND	1610	705
	ii)	NET POWER AVAILABILITY - OWN SOURCE	670	443
	",	FROM HEL	530	306
	Ī	FROM CPL/PCBL	0	0
		Import Requirement	410	27
	iii)	TOTAL AVAILABILITY	1610	776
	iv)	SURPLUS(+)/DEFICIT(-)	0	71
6		WEST BENGAL (WBSEDCL+DPL+CESC)		
		(excluding DVC's supply to WBSEDCL's command area)		
		NET MAY DEMAND	7/75	0700
	i)	NET MAX DEMAND	7675	3702
	ii)	NET POWER AVAILABILITY- Own Source	4875	2489
	1117	- Central Sector+Others	3297 407	1307 94
	iii)	SURPLUS(+)/DEFICIT(-)	497	74
7		SIKKIM		
<b>'</b>	i)	NET MAX DEMAND	90	35
	ii)	NET POWER AVAILABILITY- Own Source	3	2
	<b>1</b>	- Central Sector+Others	96	48
	iii)	SURPLUS(+)/DEFICIT(-)	9	15
	l '			
8		EASTERN REGION		
	Ī	At 1.03 AS DIVERSITY FACTOR		
	i)	NET MAX DEMAND	19112	10224
		Long term Bi-lateral by DVC	1300	874
		EXPORT BY WBSEDCL	5	3
	ii)	NET TOTAL POWER AVAILABILITY OF ER	21790	10812
	;::\	(INCLUDING C/S ALLOCATION)	1979	200
	iii)	PEAK SURPLUS(+)/DEFICIT(-) OF ER	1373	-289
	<u> </u>	(ii)-(i)		I

# Proposed Maintenance Schedule of Thermal Generating Units of ER during February, 2018 (as finalised in LGBR meeting )

System	Station	Unit	Sizo (MW)	Per	riod	No. of	Reason
System	Station	Omt	Size (MW) From To		Days	Reason	
NTPC	KhSTPS	2	210	03.02.18	27.02.18	25	Boiler, DAVR

## पावर ग्रिड कारपोरेशन ऑफ इंडिया लिमिटेड

(भारत सरकार का उद्यम)



#### POWER GRID CORPORATION OF INDIA LIMITED

(A Government of India Enterprise)

प्लाट नं.- 4, युनिट - 41, निलाद्री विहार, चंन्द्रसेखरपुर - 751021

दुरभाष : 0674 - 2720754

Plot. No. 4, Unit - 41, Niladri Vihar, Chandrasekharpur,

Bhubaneswar-751021, Tel: 0674-2720754

Ref: ODP/BB/AM/TLM/3179

Date:29th Dec 2017

To

The Member Secretary
Eastern Regional Power Committee
14, Golf Club Road

Tollygunge, Kolkata-700033

**Sub**: Request for approval of deemed availability for the insulator replacement works at NH/SH/River/Power line/Railway Crossing in various transmission lines of POWERGRID in Odisha.

Dear Sir,

During Insulator de-capping, Conductor is grounded and if such incident occurs in crossing span of other transmission line/Railway line/Road/River, consequential effects are much higher. To minimize consequential effects in case of de-Capping the above said crossing span will be provided with punctured proof Composite Long Road Polymer Insulator for which no incident of de-capping has been reported. Insulator replacement work in the above said crossings in most of the transmission lines in Odisha have been completed except few lines.

Accordingly, the s/d of the bellow mentioned lines were planned and approved in the 139<sup>th</sup> OCC meeting for replacement of porcelain insulator with Polymer insulator as follows:

SINO	Name of the line		Date	Time	Date	Time	Remark
1	400KV		10/12/2017	07:00	16/12/2017	18:00	ODB
2	Indravati 400KV		04/06/2017	07:00	06/12/2017	18:00	ODB
	Talcher C	kt#2					

Actual Shut down availed/Proposed date and time

SI	Name of the line	Date	Time	Date	Time	Remark
NO						
		19/12/2017	08:33	19/12/2017	19:34	
		20/12/2017	9:09	20/12/2017	19:56	
	400KV Rengali-	21/12/2017	7:59	21/12/2017	18:33	ODB(availed)
1	Indravati S/C	22/12/2017	08:05	22/12/2017	21:08	
		23/12/2017	9:37	23/12/2017	18:46	
		31/12/2017	8:00	31/12/2017	18:00	ODB
						(proposed)

# पावर ग्रिड कारपोरेशन ऑफ इंडिया तिमिटेड

(भारत सरकार का उद्यम)



(A Government of India Enterprise)



प्लाट नं.- 4, युनिट - 41, निलाद्री विहार, चंन्द्रसेखरपुर - 751021

दुरभाष : 0674 - 2720754

Plot. No. 4, Unit - 41, Niladri Vihar, Chandrasekharpur,

Bhubaneswar-751021, Tel: 0674-2720754

SI	Name of the line	Date Time Date			Time	Remark
NO				.0		
2	400KV Rourkela-	27/12/2017	08:42	27/12/2017	19:06	ODB(Availed)
	Talcher Ckt#2	28/12/2017	8:57	28/12/2017	18:52	

It is requested that the approved Shut down for the said lines may please be granted as deemed availability. Earlier also ERPC has granted deemed availability in same activities.

Regards.

(A.K. BEHERA)

Dy. General Manager(AM)
POWERGRID, Odisha Projects

Copy: GM(AM), POWERGRID, Odisha Projects for kind information

Det	ails of stations/U	Inits required to	operate un	der RGMO/FGMO a	as per IEGC		Whether operating under RGMO	indicate in case of status is not available
Name of State	Туре	Name of Uitlity	Sector (CS/SS/P rivate)	Name of Station	Name of Stage/ Unit	Installed capacity (MW)		
	Thermal	TVNL	SS SS	Tenughat	1 2	210 210	No No	Difficulties in implementing RGMO & exemption not
JHARKHAND	Hydro	JSEB	SS	Subarnrekha	1	65	Yes	
	Tiyaro	JOLD	SS SS	Oubannekna	2	65 82.5	Yes No	
			SS	Bandel TPS	2	82.5 82.5	No	
			SS		3	82.5	No	
			SS		4	82.5	No	
			SS SS		5 5	210 250	No No	Unit#6 could not be
				Santaldih				implemented because of
			SS		6	250	No	some technical problem
			SS	Kolaghat	2	210 210	No No	Nil Nil
			SS		3	210	No	Nil
	Termal	WBPDCL	SS		4	210	No	Nil
			SS		5	210	No	Nil
			SS SS		6	210 210	No Yes	Nil
			SS	Bakreshwar	2	210	Yes	
WEST BENGAL			SS		3	210	Yes	
			SS		4	210	Yes	
			SS SS		5	210 300	Yes No	Without OEM support it is
			SS	Sagardighi	2	300	No	not possible to put in FGMO/RGMO. At present OEM support is not
			SS		1	225	Yes	
	Hydro		SS	PPSP	2	225	Yes	In 134th OCC WBPDCL
			SS SS		3 4	225 225	Yes Yes	informed that the units are in RGMO/FGMO mode
			SS		1	250	Yes	III NGWO/I GWO IIIode
		CESC	SS	Budge-Budge	2	250	Yes	
	Thermal		SS		3	250	Yes	
			SS SS	Haldia	2	300 300	Yes Yes	
	Thermal	DPL	SS	DPL	7	300	Yes	
		OPGC	SS	IB TPS	1	210	No	Not adequate response in
		0,00	SS	15 11 0	2	210	No	RGMO
			SS SS		2	49.5 49.5	No No	
			SS		3	32	No	
			SS	Burla	4	32	No	
			SS		5	37.5	No	
			SS SS		6 7	37.5 37.5	No No	
			SS		1	60	No	
			SS		2	60	No	
			SS		3	60	No	
			SS SS	Balimela	<u>4</u> 5	60 60	No No	
0-4			SS		6	60	No	
Orissa	Hydro	OHPC	SS		7	75	No	
	riyalo	OI IF C	SS		8	75	No	
			SS SS		1 2	50 50	No No	
			SS	Rengali	3	50	No	
			SS		4	50	No	
			SS		5	50	No	
			SS		1	80	No No	
			SS SS	Upper Kolab	3	80 80	No No	
				Opper Kolab				+
			SS		4	80	No	

1	Ī	I	SS	1 [	2	150	No	
			SS	Indravati	3	150	No	
			SS		4	150	No	
		_	64	J. L.	•	100	110	
			CS	Bokaro-A	1	500	No	RGMO will be service once the unit comes in CMC mode of operation. It will be done shortly in presence of BHEL experts.
			CS		1	210	No	Not possible due to non
			cs	Bokaro-B	2	210	No	availability of Electro hydraulic governing. The
			CS		3	210	No	units will be decommissioned shortly.
			CS		2	140	No	Not possible due to non
			CS	CTPS	3	140	No	availability of Electro hydraulic governing. The units will be decommissioned shortly.
			CS	1	7	250	Yes	
			CS	1	8	250	Yes	
	Thermal	DVC	CS	DTPS	4	210	No	Not possible due to non availability of Electro hydraulic governing. The units will be decommissioned shortly.
			CS		1	210	No	Not possible due to non
			CS		2	210	No	availability of Electro
			cs	Mejia	3	210	No	Action has been initiated to put in RGMO, but testing is not yet completed.
			CS		4	210	Yes	
			CS		5	250	Yes	
Central Sector			cs		6	250	Yes	
			CS	Mejia - B	7	500	Yes	_
			CS	Mojia B	8	500	Yes	
			CS	DSTPS	1	500	Yes	_
			CS	200	2	500	Yes	
			CS		1	500	Yes	_
			CS	KODERMA	2	500	Yes	
			CS	RTPS	1	600	Yes	_
		4	CS	_	2	600	Yes	2010
	Hydro		CS	Panchet	1	40	No	RGMO mode of operation
			CS		2	40	No	would not be possible for
			CS	o	1	200	Yes	
			CS	Farakka STPP-I	2	200	Yes	
			CS		3	200	Yes	
			CS CS	Farakka STPP-II	2	500	Yes Yes	
			CS	Farakka-U#6	2	500 500	Yes	Kept in RGMO mode from April, 2014
	<b>-</b>	. ITDO	CS CS		1 2	210 210	Yes Yes	
	Thermal	NTPC	CS	1	3	210	Yes	
			CS	Kahalgoan STPP	4	210	Yes	
			CS	-	5	500	Yes	
			CS		6	500	Yes	
			CS		7	500	Yes	
			CS	Talcher STPP Stg-I	1	500	Yes	
			CS		2	500	Yes	
			CS	Barh	5	660	Yes	
		1	CS	Barh	6	660	Yes	
	ļ ,	,	CS	,	1	170	Yes	
	Hydro	NHPC	CS	Teesta HEP	2	170	Yes	
		<del>                                     </del>	cs <b>45</b>		3	170	Yes	
		<del>1</del>	PS		1	525	Yes	+
		1	PS	Maithon RB TPP	2	525	Yes	+
		1	PS		1	600	Yes	+
			PS	<b> </b>	2	600	Yes	+
	Thermal	IPP	PS	Sterlite	3	600	Yes	+
		1	PS	†	4	600	Yes	
		1	PS		1	270	Yes	
		1	PS	Adhunik Power	2	270	Yes	<b></b>
			<u> </u>			2.0		

### **Annexure-B35**

			PS	JLHEP	1	48	No	(RoR project with 3 hours	
IPP			PS	JEHLE	2	48	No	pondage)	
" '			PS	Chujachen HEP	1	49.5	No	(RoR project with 3 hours	
		IPP	PS	Chujachen HEF	2	49.5	No	pondage)	
	Lhudua		PS	Teesta Urja	1	200	No	could be put in RGMO	
			PS		PS 3	2	200	No	mode but because of
	Hydro		PS			Toosto Urio	3	200	No
			PS			4	200	No	constraint RGMO/FGMO is
			PS		5	200	No	disabled	
			PS		6	200	No	disabled	
			PS	Dikchu	1	48	No	(RoR project with 3 hours	
			PS	DIKCHU	2	48	No	pondage)	

### **AVAILABILITY STATUS OF EVENT LOGGER, DISTURBANCE RECORDER & GPS**

	Protection & Control System							
SI.	Substation		ailability				nization	Remarks
NO		EL	DR	GPS	Relay	DR	EL	
1	Subhasgram	Yes	Yes	Yes	Yes	Yes	Yes	
2	Maithon	Yes	Yes	Yes	Yes	Yes	Yes	
3	Durgapur	Yes	Yes	Yes	Yes	Yes	Yes	
4	Malda	Yes	Yes	Yes	Yes	Yes	Yes	
5	Dalkhola	Yes	Yes	Yes	Yes	Yes	Yes	
6	Siliguri	Yes	Yes	Yes	Yes	Yes	Yes	
7	Binaguri	Yes	Yes	Yes	Yes	Yes	Yes	
8	Birpara	Yes	Yes	Yes	Yes	Yes	Yes	
9	Gangtok	Yes	Yes	Yes	Yes	Yes	Yes	
10	Baripada	Yes	Yes	Yes	Yes	Yes	Yes	
11	Rengali	Yes	Yes	Yes	Yes	Yes	No	New EL would be implemented in BCU under NTAMC project by March'2015
12	Indravati (PGCIL)	Yes	Yes	Yes	Yes	Yes	No	EL is old one(model-PERM 200), provision for time synchronisation is not available. New EL would be implemented in BCU under NTAMC project by March'2015
13	Jeypore	Yes	Yes	Yes	Yes	Yes	Yes	EL is old and not working satisfactorily. New EL would be implemented in BCU under NTAMC project by March, 2015
14	Talcher	Yes	Yes	Yes	Yes	Yes	Yes	
15	Rourkela	Yes	Yes	Yes	Yes	Yes	Yes	
16	Bolangir	Yes	Yes	Yes	Yes	Yes	Yes	
17	Patna	Yes	Yes	Yes	Yes	Yes	Yes	
18	Ranchi	Yes	Yes	Yes	Yes	Yes	Yes	
19	Muzaffarpur	Yes	Yes	Yes	Yes	Yes	Yes	
20	Jamshedpur	Yes	Yes	Yes	Yes	Yes	Yes	
21	New Purnea	Yes	Yes	Yes	Yes	Yes	Yes	
22	Gaya	Yes	Yes	Yes	Yes	Yes	Yes	
23	Banka	Yes	Yes	Yes	Yes	Yes	Yes	
24	Biharsariif	Yes	Yes	Yes	Yes	Yes	Yes	
25	Barh	Yes	Yes	Yes	Yes	Yes	Yes	
26	Sagardighi	No	Yes	Yes	Yes	Yes	No	EL is under process of restoration with help from OEM, China
27	Kahalgaon	Yes	Yes	Yes	Yes	Yes	Yes	
28	Farakka	Yes	Yes	No	No	No	No	Time synchronization available for Farakka-Kahalgaon line-III & IV. The same will be implemented in rest of the lines by December, 2014.
29	Meramundali	Defunct	Yes	Yes	Yes	Yes	Yes	
30	Tisco	Yes	Yes	Yes	Yes	Yes	Yes	
31	Bidhannagar	No	Yes	Yes	No	No	No	Using DR & EL available in Numerical

					1			
								relays. GPS will be put in service by January, 2015.
32	Indravati (OHPC)	Yes	Faulty	No	No	No	No	Time synchronization will be done by Feb, 2015. ICT-I feeders using DR & EL available in Numerical relays. 400 kV ICT-II feeder is being maintained by PGCIL, Mukhiguda.Status may confirm from PGCIL
33	Kharagpur	No	Yes	Yes	No	No	No	Using DR & EL available in Numerical relays.
34	DSTPS	Yes	Yes	Yes	Yes	Yes	Yes	
35	Sterlite	Yes	Yes	Yes	Yes	Yes	Yes	
36	Mejia 'B'	Yes	Yes	Yes	Yes	Yes	Yes	
37	Mendhasal	Defunct	Yes	Yes	Yes	Yes	No	EL will be restored by March, 2015.
38	Arambagh	No	Yes	Yes	No	No	No	Using DR & EL available in Numerical relays
39	Jeerat	No	Yes	No	No	No	No	Using DR & EL available in Numerical relays. Procurement of new GPS is in progress.
40	Bakreswar	Yes	Yes	Yes	Yes	Yes	Yes	
41	GMR	Yes	Yes	Yes	Yes	Yes	Yes	
42	Maithon RB	Yes	Yes	Yes	Yes	Yes	Yes	
43	Raghunathpur	Yes	Yes	Yes	Yes	Yes	Yes	
44	Kolaghat	Yes	Yes	Yes	Yes	Yes	Yes	
45	Teesta V	Yes	Yes	Yes	Yes	Yes	Yes	
46	Koderma	Yes	Yes	Yes	Yes	Yes	Yes	
47	Sasaram	Yes	Yes	Yes	Yes	Yes	Yes	
48	Rangpo	Yes	Yes	Yes	Yes	Yes	Yes	
49	Adhunik	Yes	Yes	Yes	Yes	Yes	Yes	
50	JITPL	Yes	Yes	Yes	Yes	Yes	Yes	
51	765kV Angul	Yes	Yes	Yes	Yes	Yes	Yes	
52	Chuzachen	Yes	Yes	Yes	No	Yes	Yes	
53	New Ranchi 765kV	Yes	Yes	Yes	Yes	Yes	Yes	
54	Lakhisarai	Yes	Yes	Yes	Yes	Yes	Yes	
55	Chaibasa							
56	765kV Jharsuguda	Yes	Yes	Yes	Yes	Yes	Yes	All are in working condition. However a dedicated DR for 765KV Lines; make TESLA is not working. M/s Siemens has assured to commission the same by 31.01.15
57	Beharampur	Yes	Yes	Yes	Yes	Yes	Yes	
58	Keonjhar	Yes	Yes	Yes	Yes	Yes	Yes	

#### **Eastern Regional Power Committee**

The status of ERS towers in Eastern Region as updated in OCC meetings is given below:

1) ERS towers available in Powergrid S/s is as given below:

SI. No.	Name of S/S	No. of ERS towers available	ERS towers in use
1	Durgapur, ER-II	1 Set (8 towers)	
2	Rourkela, ER-II	3 towers incomplete shape	
3	ER-I (located at Jamshedpur)	15 towers (10 nos Tension tower and 5 nos suspension tower)	

- 2) The present status of ERS towers in OPTCL system is as follows:
- ➤ 220 kV ERS towers: 42 nos located at Mancheswar, Chatrapur & Budhipadar
- ➤ 400 kV ERS towers: 2 nos located at Mancheswar.
- > 12 nos. of new 400 kV ERS towers have been recieved.

Another, 16 nos of 400 kV towers accompanied with 6 sets of T&P are required which is under process

- 3) WBSETCL informed that they have placed order for 2 sets of ERS towers on 31.10.2014 and expected by June, 2015.
- 4) The 25<sup>th</sup> ERPC meeting held on 21.09.2014, the board concurred to the proposal of procurement of four sets of ERS and it was also informed that, the proposed four sets of ERS will be kept at Sikkim, Siliguri, Ranchi and Gaya and will be used by all constituents of ER during emergencies.

Powergrid informed that four sets of ERS for Eastern Region will be procured.

5) DVC informed that they are in process of procuring two (2) sets of 400 kV ERS towers.

## **Availability of Emergency Restoration System in BSPTCL system**

Sl. No.	Type	Quantity	Remarks
1	Tension ERS Tower	12	New
2	Suspension ERS Tower	20	New
3	Old ERS Tower	10	1 no. is defective
	Total	42	

#### Note:-

- As informed in ERS meeting held on 10-11-2014 taken by Member (Power System), CEA; 2 sets (12 tension & 20 suspension) of ERS towers had been procured and is currently available in our system (as mentioned in above table with remarks "New").
- Same ERS tower is used in both 220 Kv and 132 kV circuits.