

पूर्वी क्षेत्रीय विद्युत समिति/ Eastern Regional Power Committee
14, गोल्फ क्लब रोड , टॉलीगंज/ 14, Golf Club Road, Tollygunge,
कोलकाता - 700033/ Kolkata-700033

No. ERPC/SE (Admin.)/CPWD/2021-22/ 154

Dated, the 4th March 2022.

विषय : पू क्षे वि स कार्यालय भवन में चौथी मंजिल पर मरमत कार्य के लिए कोटेशन

Subject: Quotation for repairing work at 4th floor in ERPC office building.

Sealed quotation(s) are invited from reputed Agencies/Contractors for repairing work at 4th floor (vacant portion) in ERPC building as per following 'Scope of Work' and Terms & Conditions:

Scope of Work:

Sl. No.	Description	Qty. (Approx.)	Unit
1	Dismantling		
1.01	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in-charge.	3.00	Cu.M
1.02	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	110.00	Sq.M
1.03	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by manual means from 4th floor to Ground floor and loading to disposal truck properly as per direction of Engineer-in-charge.	20.00	Cu.M
1.04	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	20.00	Cu.M
2.00	Civil Renovation		
2.01	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 10° landings, shelves, lintels, bands, plain window sills, up to lintel from plinth at 4 th floor excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement: 1.5 coarse sand(zone-III) derived from natural sources: 3 graded stone aggregate 20 mm nominal size derived from natural sources. (Without extra re-carriage charge for unseen obstruction) with necessary water / damp proofing solutions as suggested by client.	3.00	Cu.M
2.02	Providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification	15.00	per 50 Kg
2.03	Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, and access platform Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, balconies and access platform.	15.00	Sq.M

2.04	Re-Carriage of concrete material for unseen in accessible condition at Office premises as per direction of client.	5.00	Cu.M
2.05	Extra for providing and mixing water proofing material in cement plaster work in proportion recommended by the manufacturers.	19.00	per 50 Kg
2.06	12 mm cement plaster of mix: 1:4 (1 cement: 4 fine sand) 12 mm cement plaster of mix: 1:4 (1 cement: 4 fine sand)	60.00	Sq.M
2.07	Area of slab upto 0.50 m Providing and fixing 18 mm thick gang saw cut, mirror polished, pre-moulded and pre-polished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite stone slab colour black / Cherry/Ruby red	18.00	Sq.M
2.08	Provide & Fixing iron Bar along metal support and structure. Fabrication of same as per client's guidance	6	Set
2.09	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Min. two coats	110.00	Sq.M

Terms & Conditions:

1. The rate should be quoted item wise and as a whole including GST, as applicable.
 2. Before quoting price, you are advised to visit the site at any working day between 1100 hrs. and 16 hrs.
 3. Validity of this quotation is 30 (thirty) days.
 4. The quotation shall be sent in a sealed cover superscribing "Quotation for repairing work at ERPC office" addressing to The Superintending Engineer (Admin.), ERPC, 14, Golf Club Road, Tollygunge, Kolkata-700033 **so as to reach this office on or before 15.03.2022 by 1400 hrs and shall be opened on the same day at 1530 hrs. in presence of the interested Quotationers.**
 5. Total work shall have to be completed within 25 days after receipt of the Work Order.
 6. 100% payment shall be released through online (NEFT mode) after satisfactory completion of work and final acceptance by ERPC authority.
 7. Undersigned reserves the right to reject one or all quotations without assigning any reason thereof.
- This issues with the approval of Member Secretary, ERPC.


 04/03/2022
 अधी.अभियंता(प्रशा.)/SE(Admin.)

1. M/S, G.S. ENTERPRISE, 298, Maharani India Devi Road, Kolkata - 700060
2. M/S, S.K ENTERORISE, 5/H/5 Parikshit roy Lane Kolkata – 700015
3. M/S, AIR COND, 162 Bangur Avenue, Block- A Kolkata – 700055
4. M/S, 3 C Technologies, Plot – IID/31/1, Qube, Newtown, North 24 Parganas 700135
- ✓ 5. ERPC Web site
6. ERPC Notice Board